

## BILL OF QUANTITY

**Drilling And Pressure Grouting With Bentonite RHS Side Of Main Canal between Ch.0.100 km to Ch.0.500km of DRP.**

<b>It. No.</b>	<b>Description of Item (with brief specification and reference to book of specifications)</b>	<b>Quantity</b>	<b>Unit</b>	<b>Rate in Rs.</b>	<b>Amount in Rs.</b>
1	Drilling and grouting work in all foundations and formations. (a)Drilling 200mm or above as specified dia. hole upto required depth	5000.00	Rmt	313.70	1568500.00
2	Pressure grouting of drilled holes with prescribed proportion for grouting upto maximum pressure of 7.00 kg/cm <sup>2</sup> etc. complete with... (2) Bentonite	250.00	MT	8778.60	2194650.00
			<b>Total Amount Rs.</b>		<b>3763150.00</b>

Executive Engineer  
Deesa Irrigation Division  
Deesa