

GUJARAT STATE POLICE HOUSING CORPORATION LTD., RAJKOT.

Name of Work :- Special Repair work to Barrack at Marine Task Force Commando Center at Naliya (Hothiwandh),Dist:- Kutch .(Including Electrification)

ESTIMATED CEMENT CONSUMPTION STATEMENT

Sr. No.	Description of Item	Unit	Qty.	Cement consumption Bag/Unit	Theoretical cement required Bags.
[1]	[2]	[3]	[4]	[5]	[6]
3	Providing 10 mm thick cement PLASTER in single coat on ceilings .. at GROUND FLOOR.	Sqm	130.00	0.16	20.80
4	Providing 15 mm thick cement PLASTER in single coat on brick or concrete wall .. at GROUND FLOOR.	Sqm	117.00	0.17	19.89
5	Providing 15 mm thick cement PLASTER in single coat on brick or concrete wall .. at FIRST FLOOR.	Sqm	115.00	0.17	19.55
6	Providing 20 mm thick SAND FACED cement PLASTER on walls.. etc. Complete for any height.	Sqm	454.00	0.34	154.36
14	Providing & Laying 24" x 24" vitrified 8 mm thick tile flooring over 20mm (average) base of cement mortar 1:6 (1 cement: 6 coarse sand) on new surface or fixing on existing flooring by adhesive material including dismantling of existing flooring and jointed with color cement slurry including finished with flush pointing & cleaning the surface etc.complete for antiskid. Brand of the tiles shall be as per approved make list of GSPHCL. Shade & Size of tiles shall be as specified in tender item.Size 600mm X 600mm	Sqm	18.00	0.21	3.78
15	Providing & laying Printed / Coloured GLAZED TILES 8 mm thick in skirting, risers of steps and DADO on 10mm thick cement plaster 1: 3 (1 cement : 3 coarse sand) & jointed with white cement slurry.(300mm x 600mm)	Sqm	126.00	0.19	23.94
16	P & L 24" x 24" Double Charge vitrified 8 to 10 mm thick tile flooring over 20 mm (average) base of cement mortar 1:6 (1 cement: 6 coarse sand) on new surface or fixing on existing flooring by adhesive including dismantling of	Sqm	242.00	0.21	50.82
17	P & L 24" x 24" in Skirting riser of steps and dado Double Charge vitrified 8 to 10 mm thick tile over 10 mm thick Cement plaster of cement mortar 1:3 (1 cement: 3 coarse sand) jointed with color cement slurry including finished with flush pointing & cleaning the surface etc. complete Brand of the tiles shall be as per approved make list of GSPHCL. Shade & Size of tiles shall be as specified in tender item.	Sqm	13.75	0.19	2.61
24	Constructing brick masnory chamber for under ground .. (I) inside dimensions 455mm x 610mm and 450mm deep for Single or multi purpose pipe line. Rate Also Inclusive RCC Frame with cover MD 10 ton (Rubber mould Finish) Inner Size 600 x 450mm with all necessary fittings	Nos	6.00	1.42	8.52

Sr. No.	Description of Item	Unit	Qty.	Cement consumption Bag/Unit	Theoretical cement required Bags.
[1]	[2]	[3]	[4]	[5]	[6]
29	Providing & Fixing Single Hole Wash Basin with C.I or M.S. brackete & M. I . fisher union, P.V.C water pipe with Connection from Stop Cock to Pillar Tap,PVC Bottle Trap with connection 32mm dia. C.P. brassa waste coupling with Connection 32mm dia waste Pipe up to N.T etc. Complete. Rate are inclusive of all matreials, Labour & Necessary Fittings etc. Complet as per Detailed Drawings, Specifications and as per the Instruction of Engineer In charge. Materials used for the above items Must be list approved by G.S.P.H.C.L.	Nos	3.00	0.05	0.15
				Total=	304.42
				Say=	305.00

Signature of the Contractor

I/C Executive Engineer
GSPHC Ltd Rajkot