



GUJARAT STATE POLICE HOUSING CORPORATION LTD., RAJKOT



NAME OF WORK :- SR work For Water Supply Line From E-01 Garden Bore to Exiting water Sump at SRP Group 17 ,Chela. Dist.:- Jamnagar. (Including Electrification work)

Statement showing the standard specification with Item No.& Para No. with reference to standard specification to the item description shall be as specified for in column No.3,4& 5.

| It. No | Description of Item | Page No. | Specification Item No. | Para No. | Amendment in para column No.5 & specification binding to the contractor. | Remarks |
|--------|---|----------|------------------------|------------|---|---------|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 1 | Excavation for foundation upto 1.5 M. depth including sorting out and stacking of useful materials and disposing of the excavated stuff of any lead and lift [B] Dense or Hard Soil | 62 | 2[4.0.0(B)] | 1.0 to 3.0 | At the time of excavation, if ground water found, same shall be dewatered by Agency without any extra cost. disposing of the exccavated stuf up to any lead and lift. Rate inclusive of disposing of surplus earth from site upto any lead. | |
| 2 | Excavation for foundation upto 1.5 M. depth including sorting out and stacking of useful materials and disposing of the excavated stuff of any lead and lift [C] Hard Murrum | 62 | 3[4.0.0(C)] | 1.0 to 3.0 | At the time of excavation, if ground water found, same shall be dewatered by Agency without any extra cost. disposing of the exccavated stuf up to any lead and lift. Rate inclusive of disposing of surplus earth from site upto any lead. | |
| 3 | Filling available excavated earth (excluding rock) in trenches, plinth sides of foundation etc. in layers No.t exceeding 20 cms. in depth consolidation each deposited layer by ramming and watering. | 67-68 | 23[4.12] | 1.0 To 2.0 | ---- | |
| 4 | Providing & fixing to wall celing, floor & trenches CPVC pipes SDR 13.5 ISI mark of following out side dia. Tube fittings & clamps with all as per required fitting such as reducing coupler , union,band plug, end cap ,pipe clip,tee, hex niple,elbow,coupler,etc.complete with using bonding materials rates are including of making good the wall ceiling & floor etc. Complete (excavation of earth in trenches and filling will be paid separately) (Open or concealed) 50.00 mm inner dia. | 157 | 34[23.28 (D)] | ---- | CPVC Pipes are to be used despite of UPVC. C PVC Pipes Confirming to SDR-13.5 ISI Mark only are to be provided.Including Z-patti and necessary fitiings. | |

| It. No | Description of Item | Page No. | Specification Item No. | Para No. | Amendment in para column No.5 & specification binding to the contractor. | Remarks |
|---------------|---|-----------------|-------------------------------|-----------------|---|----------------|
| 1 | 2 | 3 | 4 | 5 | 6 | 7 |
| 5 | Constructing brick masnory chamber for under ground C.I.Inspection chamber and bends with Brick having crushing strength not less than 35 Kg/Sq.cm.in cement mortar 1:5,RCC top slab with1:3:6 in cement mortar 1:5 (cover with 8 mm dia. steel @ 15 c/c and R.C.C. top slab with 1:2:4 mix (1 cement : 2 coarse sand,4- stone aggregates 20mm nominal size) foundation cocrete 1:5:10 inside laster 15 mm th. c:m 1:3 finished smooth with a floating coat of neat cement on walls & bed concrete etc. complete. Rate are also inclusive of outside plaster 15mm thick in C.M 1:3 from top of chamber and all side upto 45cm deep below ground level (I) inside dimensions 455mm x 610mm and 450mm deep for Single or multi purpose pipe line. Rate Also Inclusive RCC Frame with cover MD 10 ton (Rubber mould Finish) Inner Size 600 x | 172 | 17[24.10(C)] | 1.0 to 3.0 | Precast RCC cover shall be used instead of C.I. cover | |
| 6 | Providing and fixing gun metal check or non return full way WHEEL / HANDLE VALVE 50 mm dia. | 155 | 27[23.22(E)] | 1.0 to 3.2 | Only ISI make valve shall be used joint shall be sealed by pipe sealent. | |

Signature of Contractor

I/C. Executive Engineer
Gujarat State Police Housing Corporation Ltd.
Rajkot