

GUJARAT STATE POLICE HOUSING CORPORATION LTD., RAJKOT.**NAME OF WORK :- SR work For E-01 Garden Bore to Exiting water Sump of water supply line at SRP Group 17 ,Chela. Dist.:- Jamnagar. (Including Electrification work)****ESTIMATED CEMENT CONSUMPTION STATEMENT**

Sr.No..	Description of Item	Unit	Qty.	Cement consumption Bag/Unit	Theoretical cement required Bags.
[1]	[2]	[3]	[4]	[5]	[6]
8	Constructing brick masnory chamber for under ground C.I.Inspection chamber and bends with Brick having crushing strength not less than 35 Kg/Sq.cm.in cement mortar 1:5,RCC top slab with1:3:6 in cement mortar 1:5 (cover with 8 mm dia. steel @ 15 c/c and R.C.C. top slab with 1:2:4 mix (1 cement : 2 coarse sand,4- stone aggregates 20mm nominal size) foundation cocrete 1:5:10 inside laster 15 mm th. c:m 1:3 finished smooth with a floating coat of neat cement on walls & bed concrete etc. complete. Rate are also inclusive of outside plaster 15mm thick in C.M 1:3 from top of chamber and all side upto 45cm deep below ground level (I) inside dimensions 455mm x 610mm and 450mm deep for Single or multi purpose pipe line. Rate Also Inclusive RCC Frame with cover MD 10 ton (Rubber mould Finish) Inner Size 600 x 450mm with all necessary fittings	Nos	2.00	1.42	2.84
				Total Bags	2.84
				Say Bags	3.00

Signature of Contractor**Dy. Ex. Engineer
G.S.P.H.C.Ltd.
Jamkhambhalia****I/C Executive Engineer
G.S.P.H.C.Ltd.
Rajkot**