

**Annual Rate of Asphalt Work for the maintenance of Roads Under
(R&B) Division Jamnagar. (Year 2026-27)**

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
1	1 A	Providing & laying 37.5 mm Thick B.U.S.G (Manually) Patch work on road site using Bitumin for tack coat at the rate of 2.5Kg/10sqm. on Existing Road surface & with spreading stone aggregate at the rate of 0.50Cum./10 sqm. with dry rolling and spraying bitumin over it and spraying bitumin over it at the rate of 15 kg/10sqm. and then spreading over it stone aggregate at the rate of 0.13cum/10 Sqmt of key aggregate on top in accordance with the requirement of specification incl. cost of stone aggregate bitumin consolidation with vibratory roller necessary firrwood labour charges machineries equipment tools etc. complete.(lead 0/00 to 15/00 km)	Sqm.		
2	1 B	Providing & laying 37.5 mm Thick B.U.S.G (Manually) Patch work on road site using Bitumin for tack coat at the rate of 2.5Kg/10sqm. on Existing Road surface & with spreading stone aggregate at the rate of 0.50Cum./10 sqm. with dry rolling and spraying bitumin over it and spraying bitumin over it at the rate of 15 kg/10sqm. and then spreading over it stone aggregate at the rate of 0.13cum/10 Sqmt of key aggregate on top in accordance with the requirement of specification incl. cost of stone aggregate bitumin consolidation with vibratory roller necessary firrwood labour charges machineries equipment tools etc. complete.(lead 15/00 to 30/00 km)	Sqm.		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
3	1 C	Providing & laying 37.5 mm Thick B.U.S.G(Manually) Patch work on road site using Bitumin for tack coat at the rate of 2.5Kg/10sqm. on Existing Road surface & with spreading stone aggregate at the rate of 0.50Cum./10 sqm. with dry rolling and spraying bitumin over it and spraying bitumin over it at the rate of 15 kg/10sqm. and then spreading over it stone aggregate at the rate of 0.13cum/10 Sqmt of key aggregate on top in accordance with the requirement of specification incl. cost of stone aggregate bitumin consolidation with vibratory roller necessary firrwood labour charges machineries equipment tools etc. complete.(lead 30/00 to 50/00 km)	Sqm.		
4	1 D	Providing & laying 37.5 mm Thick B.U.S.G (Manually) Patch work on road site using Bitumin for tack coat at the rate of 2.5Kg/10sqm. on Existing Road surface & with spreading stone aggregate at the rate of 0.50Cum./10 sqm. with dry rolling and spraying bitumin over it and spraying bitumin over it at the rate of 15 kg/10sqm. and then spreading over it stone aggregate at the rate of 0.13cum/10 Sqmt of key aggregate on top in accordance with the requirement of specification incl. cost of stone aggregate bitumin consolidation with vibratory roller necessary firrwood labour charges machineries equipment tools etc. complete.(lead 50/00 to 100/00 km)	Sqm		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
5	2 A	Providing and laying and rolling 37.50mm thick bituminous groutin with B.T. aggregate as per Required Gradation and using bitumen Grade VG-30 for Mixing at the rate of 1.99% i.e. 19.90 kg/M.T. of total mix and VG-30 for tack coat at the rate of 2.5 kg/10sq.mt on existing B.T. surface including heating and mixing in Drum mix plant ,trasporting spreading same by paver finisher and consolidation by viberated roller including necessary firewood, oil,kerosene, lubricants all equipments, tools, labour charges etc. complete using contractor's own machinary in accordance with the requirement of specification.(lead 0/00 to 15/00 km)	MT		
6	2 B	Providing and laying and rolling 37.50mm thick bituminous groutin with B.T. aggregate as per Required Gradation and using bitumen Grade VG-30 for Mixing at the rate of 1.99% i.e. 19.90 kg/M.T. of total mix and VG-30 for tack coat at the rate of 2.5 kg/10sq.mt on existing B.T. surface including heating and mixing in Drum mix plant ,trasporting spreading same by paver finisher and consolidation by viberated roller including necessary firewood, oil,kerosene, lubricants all equipments, tools, labour charges etc. complete using contractor's own machinary in accordance with the requirement of specification.(lead 15/00 to 30/00 km)	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
7	2 C	Providing and laying and rolling 37.50mm thick bituminous groutin with B.T. aggregate as per Required Gradation and using bitumen Grade VG-30 for Mixing at the rate of 1.99% i.e. 19.90 kg/M.T. of total mix and VG-30 for tack coat at the rate of 2.5 kg/10sq.mt on existing B.T. surface including heating and mixing in Drum mix plant ,trasporting spreading same by paver finisher and consolidation by viberated roller including necessary firewood, oil,kerosene, lubricants all equipments, tools, labour charges etc. complete using contractor's own machinary in accordance with the requirement of specification.(lead 50/00 to 100/00 km)	MT		
8	2 D	Providing and laying and rolling 37.50mm thick bituminous groutin with B.T. aggregate as per Required Gradation and using bitumen Grade VG-30 for Mixing at the rate of 1.99% i.e. 19.90 kg/M.T. of total mix and VG-30 for tack coat at the rate of 2.5 kg/10sq.mt on existing B.T. surface including heating and mixing in Drum mix plant ,trasporting spreading same by paver finisher and consolidation by viberated roller including necessary firewood, oil,kerosene, lubricants all equipments, tools, labour charges etc. complete using contractor's own machinary in accordance with the requirement of specification.(lead 50/00 to 100/00 km)	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
9	3 A	Providing & laying 75.00 mm Thick B.U.S.G Patch work on road site using Bitumin for tack coat at the rate of 2.5Kg/10sqm. on Existing Road surface & with spreading stone aggregate at the rate of 0.50Cum./10 sqm. with dry rolling and spraying bitumin over it and spraying bitumin over it at the rate of 15 kg/10sqm for 1st layer and 15 kg / 10Sqmt for 2nd layer. and then spreading over it stone aggregate at the rate of 0.13cum/10 Sqmt of key aggregate on top in accordance with the requirement of specification incl. cost of stone aggregate bitumin consolidation with vibratory roller necessary firrwood labour charges machineries equipment tools etc. complete.(lead 0/00 to 15/00 km)	Sqm.		
10	3 B	Providing & laying 75.00 mm Thick B.U.S.G Patch work on road site using Bitumin for tack coat at the rate of 2.5Kg/10sqm. on Existing Road surface & with spreading stone aggregate at the rate of 0.50Cum./10 sqm. with dry rolling and spraying bitumin over it and spraying bitumin over it at the rate of 15 kg/10sqm for 1st layer and 15 kg / 10Sqmt for 2nd layer.. and then spreading over it stone aggregate at the rate of 0.13cum/10 Sqmt of key aggregate on top in accordance with the requirement of specification incl. cost of stone aggregate bitumin consolidation with vibratory roller necessary firrwood labour charges machineries equipment tools etc. complete.(lead 15/00 to 30/00 km)	Sqm.		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
11	3 C	Providing & laying 75.00 mm Thick B.U.S.G Patch work on road site using Bitumin for tack coat at the rate of 2.5Kg/10sqm. on Existing Road surface & with spreading stone aggregate at the rate of 0.50Cum./10 sqm. with dry rolling and spraying bitumin over it and spraying bitumin over it at the rate of 15 kg/10sqm for 1st layer and 15 kg / 10Sqmt for 2nd layer.. and then spreading over it stone aggregate at the rate of 0.13cum/10 Sqmt of key aggregate on top in accordance with the requirement of specification incl. cost of stone aggregate bitumin consolidation with vibratory roller necessary firrwood labour charges machineries equipment tools etc. complete.(lead 30/00 to 50/00 km)	Sqm.		
12	3 D	Providing & laying 37.5 mm Thick B.U.S.G Patch work on road site using Bitumin for tack coat at the rate of 2.5Kg/10sqm. on Existing Road surface & with spreading stone aggregate at the rate of 0.50Cum./10 sqm. with dry rolling and spraying bitumin over it and spraying bitumin over it at the rate of 15 kg/10sqm for 1st layer and 15 kg / 10Sqmt for 2nd layer.. and then spreading over it stone aggregate at the rate of 0.13cum/10 Sqmt of key aggregate on top in accordance with the requirement of specification incl. cost of stone aggregate bitumin consolidation with vibratory roller necessary firrwood labour charges machineries equipment tools etc. complete.(lead 50/00 to 100/00 km)	Sqm.		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
13	4 A	Providing and laying and rolling 75.00mm thick bituminous groutin with B.T. aggregate as per Required Gradation and using bitumen Grade VG-30 for Mixing at the rate of 1.99% i.e. 19.90 kg/M.T. of total mix and VG-30 for tack coat at the rate of 2.5 kg/10sq.mt on existing B.T. surface including heating and mixing in Drum mix plant ,trasporting spreading same by paver finisher and consolidation by viberated roller including necessary firewood, oil,kerosene, lubricants all equipments, tools, labour charges etc. complete using contractor's own machinary in accordance with the requirement of specification.(lead 0/00 to 15/00 km)	MT		
14	4 B	Providing and laying and rolling 75.00mm thick bituminous groutin with B.T. aggregate as per Required Gradation and using bitumen Grade VG-30 for Mixing at the rate of 1.99% i.e. 19.90 kg/M.T. of total mix and VG-30 for tack coat at the rate of 2.5 kg/10sq.mt on existing B.T. surface including heating and mixing in Drum mix plant ,trasporting spreading same by paver finisher and consolidation by viberated roller including necessary firewood, oil,kerosene, lubricants all equipments, tools, labour charges etc. complete using contractor's own machinary in accordance with the requirement of specification.(lead 15/00 to 30/00 km)	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
15	4 C	Providing and laying and rolling 75.00mm thick bituminous groutin with B.T. aggregate as per Required Gradation and using bitumen Grade VG-30 for Mixing at the rate of 1.99% i.e. 19.90 kg/M.T. of total mix and VG-30 for tack coat at the rate of 2.5 kg/10sq.mt on existing B.T. surface including heating and mixing in Drum mix plant ,trasporting spreading same by paver finisher and consolidation by viberated roller including necessary firewood, oil,kerosene, lubricants all equipments, tools, labour charges etc. complete using contractor's own machinary in accordance with the requirement of specification.(lead 30/00 to 50/00 km)	MT		
16	4 D	Providing and laying and rolling 75.00mm thick bituminous groutin with B.T. aggregate as per Required Gradation and using bitumen Grade VG-30 for Mixing at the rate of 1.99% i.e. 19.90 kg/M.T. of total mix and VG-30 for tack coat at the rate of 2.5 kg/10sq.mt on existing B.T. surface including heating and mixing in Drum mix plant ,trasporting spreading same by paver finisher and consolidation by viberated roller including necessary firewood, oil,kerosene, lubricants all equipments, tools, labour charges etc. complete using contractor's own machinary in accordance with the requirement of specification.(lead 50/00 to 100/00 km)	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
17	5 A	Providing and laying 50mm thick B.M. With BT Aggregate VG-30 grade bitumen for Tack coat @ 2.50 kg/10 sqm using crushed stone aggregate 0.66 cum/ MT as per MORTH&H Specification & VG-30 grade bitumen for mixing @34.00 Kg/1 MT i.e. 3.4% of by weight of total mix incl. heating and mixing by drum mix plant and spreading the same with paver finisher consolidation with vibratory roller including cost of fuel, hire charges, all necessary equipments, tools and plant, fire wood, oil, kerosene labour changes etc complete.(Using contractor's own Machinery) (Lead 0/00 to 15/00.	MT		
18	5 B	Providing and laying 50mm thick B.M. With BT Aggregate VG-30 grade bitumen for Tack coat @ 2.50 kg/10 sqm using crushed stone aggregate 0.66 cum/ MT as per MORTH&H Specification & VG-30 grade bitumen for mixing @34.00 Kg/1 MT i.e. 3.4% of by weight of total mix incl. heating and mixing by drum mix plant and spreading the same with paver finisher consolidation with vibratory roller including cost of fuel, hire charges, all necessary equipments, tools and plant, fire wood, oil, kerosene labour changes etc complete.(Using contractor's own Machinery) (Lead 15/00 to 30/00.	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
19	5 C	Providing and laying 50mm thick B.M. With BT Aggregate VG-30 grade bitumen for Tack coat @ 2.50 kg/10 sqm using crushed stone aggregate 0.66 cum/ MT as per MORTH&H Specification & VG-30 grade bitumen for mixing @34.00 Kg/1 MT i.e. 3.4% of by weight of total mix incl. heating and mixing by drum mix plant and spreading the same with paver finisher consolidation with vibratory roller including cost of fuel, hire charges, all necessary equipments, tools and plant, fire wood, oil, kerosene labour changes etc complete.(Using contractor's own Machinery) (Lead 30/00 to 50/00.	MT		
20	5 D	Providing and laying 50mm thick B.M. With BT Aggregate VG-30 grade bitumen for Tack coat @ 2.50 kg/10 sqm using crushed stone aggregate 0.66 cum/ MT as per MORTH&H Specification & VG-30 grade bitumen for mixing @34.00 Kg/1 MT i.e. 3.4% of by weight of total mix incl. heating and mixing by drum mix plant and spreading the same with paver finisher consolidation with vibratory roller including cost of fuel, hire charges, all necessary equipments, tools and plant, fire wood, oil, kerosene labour changes etc complete.(Using contractor's own Machinery) (Lead 50/00 to 100/00.	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
21	6 A	Providing and laying 50mm thick B.M. With BT Aggregate VG-30 grade bitumen for Tack coat @ 2.50 kg/10 sqm using crushed stone aggregate 0.66 cum/ MT as per MORTH&H Specification & VG-30 grade bitumen for mixing @34.00 Kg/1 MT i.e. 3.4% of by weight of total mix incl. heating and mixing by drum mix plant and spreading the same without paver finisher consolidation with vibratory roller including cost of fuel, hire charges, all necessary equipments, tools and plant, fire wood, oil, kerosene labour changes etc complete.(Using contractor's own Machinery) (Lead 0/00 to 15/00.	MT		
22	6 B	Providing and laying 50mm thick B.M. With BT Aggregate VG-30 grade bitumen for Tack coat @ 2.50 kg/10 sqm using crushed stone aggregate 0.66 cum/ MT as per MORTH&H Specification & VG-30 grade bitumen for mixing @34.00 Kg/1 MT i.e. 3.4% of by weight of total mix incl. heating and mixing by drum mix plant and spreading the same without paver finisher consolidation with vibratory roller including cost of fuel, hire charges, all necessary equipments, tools and plant, fire wood, oil, kerosene labour changes etc complete.(Using contractor's own Machinery) (Lead 15/00 to 30/00.	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
23	6 C	Providing and laying 50mm thick B.M. With BT Aggregate VG-30 grade bitumen for Tack coat @ 2.50 kg/10 sqm using crushed stone aggregate 0.66 cum/ MT as per MORTH&H Specification & VG-30 grade bitumen for mixing @34.00 Kg/1 MT i.e. 3.4% of by weight of total mix incl. heating and mixing by drum mix plant and spreading the same without paver finisher consolidation with vibratory roller including cost of fuel, hire charges, all necessary equipments, tools and plant, fire wood, oil, kerosene labour changes etc complete.(Using contractor's own Machinery) (Lead 30/00 to 50/00.	MT		
24	6 D	Providing and laying 50mm thick B.M. With BT Aggregate VG-30 grade bitumen for Tack coat @ 2.50 kg/10 sqm using crushed stone aggregate 0.66 cum/ MT as per MORTH&H Specification & VG-30 grade bitumen for mixing @34.00 Kg/1 MT i.e. 3.4% of by weight of total mix incl. heating and mixing by drum mix plant and spreading the same without paver finisher consolidation with vibratory roller including cost of fuel, hire charges, all necessary equipments, tools and plant, fire wood, oil, kerosene labour changes etc complete.(Using contractor's own Machinery) (Lead 50/00 to 100/00.	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
25	7 A	Providing and laying 20 mm thick average for patchwork Mix seal surface using stone chips @66% by weight, gradation as per MORTH specification and using bitumin VG 30 grade for tack coat @ 2.50 Kg/10Sqm and for mixing rate not less then 50.90KG/MT on BT surface using stone chips as per MORTH specification including heating the ashphalt and aggregates by hot mix plant and spreading the same with paver finisher including consolidation wit vibratory roller and providing, operating plant machinaries, equipments, tools, plants, oil, fire wood, kerosene and all labour charges etc. complete. (Lead 0/00 to 15/00.)	MT		
26	7 B	Providing and laying 20 mm thick average for patchwork Mix seal surface using stone chips @66% by weight, gradation as per MORTH specification and using bitumin VG 30 grade for tack coat @ 2.50 Kg/10Sqm and for mixing rate not less then 50.90KG/MT on BT surface using stone chips as per MORTH specification including heating the ashphalt and aggregates by hot mix plant and spreading the same with paver finisher including consolidation wit vibratory roller and providing, operating plant machinaries, equipments, tools, plants, oil, fire wood, kerosene and all labour charges etc. complete. (Lead 15/00 to 30/00.)	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
27	7 C	Providing and laying 20 mm thick average for patchwork Mix seal surface using stone chips @66% by weight, gradation as per MORTH specification and using bitumin VG 30 grade for tack coat @ 2.50 Kg/10Sqm and for mixing rate not less then 50.90KG/MT on BT surface using stone chips as per MORTH specification including heating the ashphalt and aggregates by hot mix plant and spreading the same with paver finisher including consolidation wit vibratory roller and providing, operating plant machinaries, equipments, tools, plants, oil, fire wood, kerosene and all labour charges etc. complete. (Lead 30/00 to 50/00.	MT		
28	7 D	Providing and laying 20 mm thick average for patchwork Mix seal surface using stone chips @66% by weight, gradation as per MORTH specification and using bitumin VG 30 grade for tack coat @ 2.50 Kg/10Sqm and for mixing rate not less then 50.90KG/MT on BT surface using stone chips as per MORTH specification including heating the ashphalt and aggregates by hot mix plant and spreading the same with paver finisher including consolidation wit vibratory roller and providing, operating plant machinaries, equipments, tools, plants, oil, fire wood, kerosene and all labour charges etc. complete. (Lead 50/00 to 100/00.	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
29	8 A	Providing and laying 20 mm thick average for patchwork Mix seal surface using stone chips @66% by weight, gradation as per MORTH specification and using bitumin VG 30 grade for tack coat @ 2.50 Kg/10Sqm and for mixing rate not less then 50.90KG/MT on BT surface using stone chips as per MORTH specification including heating the ashphalt and aggregates by hot mix plant and spreading the same without paver finisher including consolidation wit vibratory roller and providing, operating plant machinaries, equipments, tools, plants, oil, fire wood, kerosene and all labour charges etc. complete., including Cutting of existing asphalt surface in required depth in Square or Rectangular shape as directed by engineer in charge as and when required. (Lead 0/00 km to 15/0)	MT		
30	8 B	Providing and laying 20 mm thick average for patchwork Mix seal surface using stone chips @66% by weight, gradation as per MORTH specification and using bitumin VG 30 grade for tack coat @ 2.50 Kg/10Sqm and for mixing rate not less then 50.90KG/MT on BT surface using stone chips as per MORTH specification including heating the ashphalt and aggregates by hot mix plant and spreading the same without paver finisher including consolidation wit vibratory roller and providing, operating plant machinaries, equipments, tools, plants, oil, fire wood, kerosene and all labour charges etc. complete., including Cutting of existing asphalt surface in required depth in Square or Rectangular shape as directed by engineer in charge as and when required. (Lead 15/00 to 30/00.)	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
31	8 C	Providing and laying 20 mm thick average for patchwork Mix seal surface using stone chips @66% by weight, gradation as per MORTH specification and using bitumin VG 30 grade for tack coat @ 2.50 Kg/10Sqm and for mixing rate not less then 50.90KG/MT on BT surface using stone chips as per MORTH specification including heating the ashphalt and aggregates by hot mix plant and spreading the same without paver finisher including consolidation wit vibratory roller and providing, operating plant machinaries, equipments, tools, plants, oil, fire wood, kerosene and all labour charges etc. complete., including Cutting of existing asphalt surface in required depth in Square or Rectangular shape as directed by engineer in charge as and when required. (Lead 15/00 to 30/00.)	MT		
32	8 D	Providing and laying 20 mm thick average for patchwork Mix seal surface using stone chips @66% by weight, gradation as per MORTH specification and using bitumin VG 30 grade for tack coat @ 2.50 Kg/10Sqm and for mixing rate not less then 50.90KG/MT on BT surface using stone chips as per MORTH specification including heating the ashphalt and aggregates by hot mix plant and spreading the same without paver finisher including consolidation wit vibratory roller and providing, operating plant machinaries, equipments, tools, plants, oil, fire wood, kerosene and all labour charges etc. complete., including Cutting of existing asphalt surface in required depth in Square or Rectangular shape as directed by engineer in charge as and when required. (Lead 50/00 to 100/00.)	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
33	9 A	Providing and laying seal coat with B.T. aggregate as specified using aggregate at the rate of 0.18 Cum/ 10 Sq.Mt. and bitumen VG-30 for mixing with aggregate at the rate of 4.5 % i.e. 45.00 Kg./M.T. of total mix including heating and mixing in drum mix plant and spreading the same by with paver finisher and consolidation with vibratory roller including necessary fire wood, oil, lubricants, labour charges using contractor's own drum mix plant, machineries and equipment, tools etc. complete in accordance with the requirement of specification. (Lead 0/00 to 15/00.	MT		
34	9 B	Providing and laying seal coat with B.T. aggregate as specified using aggregate at the rate of 0.18 Cum/ 10 Sq.Mt. and bitumen VG-30 for mixing with aggregate at the rate of 4.5 % i.e. 45.00 Kg./M.T. of total mix including heating and mixing in drum mix plant and spreading the same by with paver finisher and consolidation with vibratory roller including necessary fire wood, oil, lubricants, labour charges using contractor's own drum mix plant, machineries and equipment, tools etc. complete in accordance with the requirement of specification. (Lead 15/00 to 30/00.	MT		


Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
35	9 C	Providing and laying seal coat with B.T. aggregate as specified using aggregate at the rate of 0.18 Cum/ 10 Sq.Mt. and bitumen VG-30 for mixing with aggregate at the rate of 4.5 % i.e. 45.00 Kg./M.T. of total mix including heating and mixing in drum mix plant and spreading the same by with paver finisher and consolidation with vibratory roller including necessary fire wood, oil, lubricants, labour charges using contractor's own drum mix plant, machineries and equipment, tools etc. complete in accordance with the requirement of specification. (Lead 30/00 to 50/00.	MT		
36	9 D	Providing and laying seal coat with B.T. aggregate as specified using aggregate at the rate of 0.18 Cum/ 10 Sq.Mt. and bitumen VG-30 for mixing with aggregate at the rate of 4.5 % i.e. 45.00 Kg./M.T. of total mix including heating and mixing in drum mix plant and spreading the same by with paver finisher and consolidation with vibratory roller including necessary fire wood, oil, lubricants, labour charges using contractor's own drum mix plant, machineries and equipment, tools etc. complete in accordance with the requirement of specification. (Lead 50/00 to 100/00.)	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
37	10 A	Providing and laying seal coat with B.T. aggregate as specified using aggregate at the rate of 0.18 Cum/ 10 Sq.Mt. and bitumen VG-30 for mixing with aggregate at the rate of 4.5 % i.e. 45.00 Kg./M.T. of total mix including heating and mixing in drum mix plant and spreading the same by without paver finisher and consolidation with vibratory roller including necessary fire wood, oil, lubricants, labour charges using contractor's own drum mix plant, machineries and equipment, tools etc. complete in accordance with the requirement of specification. (Lead 0/00 to 15/00.	MT		
38	10 B	Providing and laying seal coat with B.T. aggregate as specified using aggregate at the rate of 0.18 Cum/ 10 Sq.Mt. and bitumen VG-30 for mixing with aggregate at the rate of 4.5 % i.e. 45.00 Kg./M.T. of total mix including heating and mixing in drum mix plant and spreading the same by without paver finisher and consolidation with vibratory roller including necessary fire wood, oil, lubricants, labour charges using contractor's own drum mix plant, machineries and equipment, tools etc. complete in accordance with the requirement of specification. (Lead 15/00 to 30/00.	MT		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
39	10 C	Providing and laying seal coat with B.T. aggregate as specified using aggregate at the rate of 0.18 Cum/ 10 Sq.Mt. and bitumen VG-30 for mixing with aggregate at the rate of 4.5 % i.e. 45.00 Kg./M.T. of total mix including heating and mixing in drum mix plant and spreading the same by without paver finisher and consolidation with vibratory roller including necessary fire wood, oil, lubricants, labour charges using contractor's own drum mix plant, machineries and equipment, tools etc. complete in accordance with the requirement of specification. (Lead 30/00 to 50/00.	MT		
40	10 D	Providing and laying seal coat with B.T. aggregate as specified using aggregate at the rate of 0.18 Cum/ 10 Sq.Mt. and bitumen VG-30 for mixing with aggregate at the rate of 4.5 % i.e. 45.00 Kg./M.T. of total mix including heating and mixing in drum mix plant and spreading the same by without paver finisher and consolidation with vibratory roller including necessary fire wood, oil, lubricants, labour charges using contractor's own drum mix plant, machineries and equipment, tools etc. complete in accordance with the requirement of specification. (Lead 50/00 to 100/00.	MT		
41	11 A	Providing and laying asphalt painting on BT surface with Bitumin grade VG-30 at the rate of 5.00 kg/10 sqm by mechanical sprayer and spreading the stone dust on prepared surface at the rate 0.03 cum/10 sqm and rolling with PTR roller & brushing etc. complete. (Lead 0/00 to 15/00.)	Sqm.		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
42	11 B	Providing and laying asphalt painting on BT surface with Bitumin grade VG-30 at the rate of 5.00 kg/10 sqm by mechanical sprayer and spreading the stone dust on prepared surface at the rate 0.03 cum/10 sqm and rolling with PTR roller & brushing etc. complete.(Lead 15/00 to 30/00.)	Sqm.		
43	11 C	Providing and laying asphalt painting on BT surface with Bitumin grade VG-30 at the rate of 5.00 kg/10 sqm by mechanical sprayer and spreading the stone dust on prepared surface at the rate 0.03 cum/10 sqm and rolling with PTR roller & brushing etc. complete.(Lead 30/00 to 50/00.)	Sqm.		
44	11 D	Providing and laying asphalt painting on BT surface with Bitumin grade VG-30 at the rate of 5.00 kg/10 sqm by mechanical sprayer and spreading the stone dust on prepared surface at the rate 0.03 cum/10 sqm and rolling with PTR roller & brushing etc. complete.(Lead 50/00 to 100/00.)	Sqm.		
45	12 A	Providing and laying asphalt painting on BT surface with Bitumin grade VG-30 at the rate of 5.00 kg/10 sqm by mechanical sprayer and spreading the stone dust on prepared surface at the rate 0.03 cum/10 sqm and rolling with PTR roller & brushing etc. complete. (Lead 0/00 to 15/00.)	Cum		
46	12 B	Providing and laying asphalt painting on BT surface with Bitumin grade VG-30 at the rate of 5.00 kg/10 sqm by mechanical sprayer and spreading the stone dust on prepared surface at the rate 0.03 cum/10 sqm and rolling with PTR roller & brushing etc. complete.(Lead 15/00 to 30/00.)	Cum		

Sr. No.	It. No.	Description of Item	Unit	Net Rate	Rupees in Words
47	12 C	Providing and laying asphalt painting on BT surface with Bitumin grade VG-30 at the rate of 5.00 kg/10 sqm by mechanical sprayer and spreading the stone dust on prepared surface at the rate 0.03 cum/10 sqm and rolling with PTR roller & brushing etc. complete.(Lead 30/00 to 50/00.)	Cum		
48	12 D	Providing and laying asphalt painting on BT surface with Bitumin grade VG-30 at the rate of 5.00 kg/10 sqm by mechanical sprayer and spreading the stone dust on prepared surface at the rate 0.03 cum/10 sqm and rolling with PTR roller & brushing etc. complete.(Lead 50/00 to 100/00.)	Cum		


 Deputy Executive Engineer
 Jamjodhpur (R & B) Sub-Division
 Jamnagar

કામનું નામ:— એન્યુઅલ રેટ ઓફ આસ્ફાલ્ટ વર્ક ફોર ધી મેઈન્ટેનન્સ ઓફ રોડસ અન્ડર (આર.એન્ડ બી.) ડીવીઝન, જામનગર ડી.જામનગર. (વર્ષ ૨૦૨૬-૨૭).

—: શરતો :—

- ૧) વિભાગીય કચેરીનાં કાર્યક્ષેત્રમાં આવતી તમામ નાયબ કાર્યપાલક ઈજનેરશ્રીની તાબા હેઠળના કાર્યક્ષેત્રમાં કામગીરી કરવાની રહેશે.
- ૨) નાયબ કાર્યપાલક ઈજનેરશ્રી/ સાઈટ એન્જિનીયરની લેખીત સુચના મુજબની તમામ કામગીરી કરવાની રહેશે.
- ૩) અત્રેથી લેખિત/ મૌખિક અથવા ટેલીફોનિક સુચના આપ્યાને દિવસ-૧ (એક) માં સુચવેલ કામગીરી ચાલુ કરવાની રહેશે. જો શરૂ કરવામાં નહીં આવે તો જે તે એજન્સીની ડીપોઝીટ જપ્ત કરી કાળીયાદીમાં મુકવામાં આવશે, જે અન્વયે કોઈ વાંધો/ વિરોધ ગ્રાહ્ય રાખવામાં આવશે નહીં.
- ૪) મટીરીયલ્સનાં ટેસ્ટ રીઝલ્ટ નિયમોનુસાર પેટા વિભાગીય કચેરી સાથે સંકલન કરી રજૂ કરવાનાં રહેશે. મીક્ષ ડિઝાઈન માટે ટેસ્ટીંગ ચાર્જ એજન્સીએ ભોગવવાનો રહેશે.
- ૫) ભરેલ ભાવો સરકારી ટેક્સ લેબર સેસ સહિત અને જી.એસ.ટી. વગરનાં આપવાનાં રહેશે. બીલ રજૂ કરતી વખતે બીલ જી.એસ.ટી. વાળુ રજૂ કરવાનું રહેશે.
- ૬) બાનાની રકમ રૂ. ૫,૦૦,૦૦૦/- ની ટેન્ડર સાથે ભરવાની રહેશે.
- ૭) જે ઈજારદારનાં ભાવો મંજૂર થાય તેને રૂ. ૫,૦૦,૦૦૦/- ની એફ.ડી.આર. ૧-વર્ષની મુદતની ડીપોઝીટ તરીકે જમાં કરાવવાની રહેશે. જે ભાવની માન્યતા પૂર્ણ થયાનાં એક વર્ષ બાદ પરત કરવામાં આવશે. તથા કામનાં બીલોમાંથી એસ.ડી.ની કપાત કરવામાં નહીં આવે.
- ૮) આસામી ધ્વારા નિયત સમયમાં કામગીરી પૂરી પાડવામાં નહીં આવે તો રૂ. ૨૦૦/- દિવસ એકની પેનલ્ટી લાગુ પડશે અને ભરેલ ડીપોઝીટ જપ્ત કરવામાં આવશે.
- ૯) મંજૂર થયેલ ભાવથી કામ કરતા પહેલા વિભાગીય કચેરીએથી જરૂરી પેટ્રોલ/ તાંત્રિક મંજૂરી મેળવી પેટા વિભાગ ધ્વારા જરૂરી એગ્રીમેન્ટ કરી, વર્ક ઓર્ડર મેળવી કામ કરવાનું રહેશે.
- ૧૦) મંજૂર થયેલા ભાવોની મુદત મંજૂરીની તારીખથી ૧૨(બાર) માસની મુદતનાં રહેશે, ત્યાર બાદ જો જરૂરી જણાય તો બન્ને પક્ષોની સહમતી હોય તો ભાવોની મુદત ૬(છ) માસ વધારી શકાશે.
- ૧૧) ટેન્ડર મંજૂર કરવું, ન કરવું તેનો સક્ષમ અધિકારીશ્રીને અબાધિત હકક રહેશે.
- ૧૨) ભાવો મંજૂર થયેલ એજન્સીએ મીક્ષ માલ માન્ય મીકેનીકલ ખાતાનું પ્રમાણપત્ર ધરાવતા એચ.એમ./ ડી.એમ. પ્લાન્ટેથી જ લાવવાનો રહેશે તેમજ જરૂરી દસ્તાવેજ આપવાનાં રહેશે.
- ૧૩) કામ દરમ્યાન પબ્લિક કે પર્યાવરણને નુકશાન ન થાય તેની તકેદારી રાખવાની રહેશે તેમજ જો આ અંગે કોઈ પ્રશ્નો ઉપસ્થિત થશે તો તેની જવાબદારી જે તે એજન્સીની રહેશે.
- ૧૪) કામગીરી દરમ્યાન અકસ્માત કે અન્ય કોઈ પ્રશ્ન ઉપસ્થિત થશે તો તેની જવાબદારી જે તે એજન્સીની રહેશે તે બાબતે સરકારશ્રીની કોઈ પણ જવાબદારી રહેશે નહીં તેમજ મજૂરો કારીગરોનો નિયમોનુસાર લાયસન્સ મેળવી લેવાનું રહેશે તથા તે જે તે નાયબ કાર્યપાલક ઈજનેરશ્રીને કામગીરી શરૂ કરતા પહેલા લેબર લાયસન્સ સાદર કરવાનું રહેશે.

- ૧૫) નિયમોનુસારનું કરારખત કરવાનું રહેશે તથા તે કામ માર્ગ અને મકાન વિભાગના માન્ય રોડ સ્પેશીફિકેશન મુજબ કરવાના રહેશે.
- ૧૬) બાનાની રકમ વગરનું ભાવપત્રક માન્ય રાખવામાં આવશે નહીં.
- ૧૭) કોઈપણ શરતી ભાવો સ્વીકારવામાં આવશે નહીં.
- ૧૮) ખાસ કિસ્સામાં અગત્યતાના ધોરણે હાથ ધરવાની થતી કામગીરી જો ટુંકી સમયમર્યાદામાં પૂર્ણ કરવાનો પ્રશ્ન ઉપસ્થિત થાય ત્યારે તે સોર્પેલ સમયમર્યાદામાં પૂર્ણ કરવાનું રહેશે.
- ૧૯) કામમાં વાપરવામાં આવેલ માલ સામાન જો રોયલ્ટી ચુકવવાપાત્ર હોય તો તેની સંપૂર્ણ જવાબદારી જે તે આસામીની રહેશે.
- ૨૦) કામમાં વાપરવામાં આવેલ ડામરનો રેટ એસકેલેશન અલગથી ચુકવવામાં આવશે નહીં તે સમજીને ભાવો ભરવાના રહેશે.
- ૨૧) કામમાં વાપરવામાં આવેલ ડામર ખરીદીનાં માન્ય રીફાઈનરી/ કંપનીનાં અસલ ગેઈટ પાસ બીલ સાથે રજૂ કરવાનાં રહેશે.
- ૨૨) કામનાં શરૂઆત તથા કામ પૂર્ણ થયા બાદ કરેલ કામગીરીના ફોટોગ્રાફ્સ રજૂ કરવાના રહેશે.
- ૨૩) ભાવપત્રકમાં દર્શાવવામાં જથ્થો માત્ર યુનિટ માટેનો છે તે સિવાયની વધારાની કામગીરીનો જથ્થો જ્યારે જ્યારે કરવાનો થાય ત્યારે ઈજારદારે આ ભરેલ ભાવે પેટા કચેરીની સુચના મુજબના સ્થળે કામગીરી કરી આપવાની રહેશે.
- ૨૪) ભાવ સમજી વિચારીને ભરવાના રહેશે વધારે ઉંચા/નીચા ભાવો બાબતે રેઈટ એનાલીસીસ આપવાનું રહેશે તથા તે બાબતે કોઈ વાંધો ચલાવવામાં આવશે નહીં તથા તે બાબતનું પ્રમાણપત્ર આપવાનું રહેશે કે "મેં ભાવો ચકાસણી કરી સમજી વિચારીને ભરેલ છે. તથા ભરેલ ભાવોએ કામ કરવા સંમત છું અન્યથા મારી ડિપોઝીટ જપ્ત કરી અને કાળીયાદીમાં મુકવામાં આવશે તો તે બાબતે હું કોઈ દાદ,ફરીયાદ,લવાદ કે કોર્ટ કેઈસ કરીશ નહીં."
- ૨૫) કામની અગત્યતા તથા જરૂરીયાત હોય તો અન્ય ઈજારદારશ્રી પાસે મંજૂર થયેલ ભાવથી કામગીરી કરાવી શકાશે તેમાં સીક્યોરીટી ડિપોઝીટ ૧૦% કપાત કરવામાં આવશે. તે બાબતે ભાવો મંજૂર થયેલ એજન્સી ધ્વારા કોઈ વાંધો કે તકરાર લેવાનાં રહેશે નહીં.
- ૨૬) કોઈ વિવાદ અંગે જયુરીડિકશન જામનગર રહેશે.
- ૨૭) સદરહુ કામમાં ઈજારદારશ્રીને પ્રાઈઝ વેરીએશન અથવા સ્ટાર રેઈટનું ચુકવણું / રીકવરી કરવાની રહેશે નહીં.

ઉપરોક્ત શરતો નં. ૧ થી ૨૭ અમોએ વાંચી છે અને અમોને કબુલ મંજૂર છે જે અમોને બંધનકર્તા રહેશે.

ઠેકેદારની સહી :

કાર્યપાલક ઈજનેર
જામનગર (મા. અને મ.) વિભાગ
જામનગર

કામનું નામ:— એન્યુઅલ રેટ ઓફ આસ્ફાલ્ટ વર્ક ફોર ઘી મેઈન્ટેનન્સ ઓફ રોડસ અન્ડર (આર.એન્ડ બી.) ડીવીઝન, જામનગર ડી.જામનગર. (વર્ષ ૨૦૨૬-૨૭).

પ્રિ-કવોલીફિકેશન માટે અપલોડ કરવાના દસ્તાવેજોની વિગત

અ.નં.	દસ્તાવેજોની વિગત
૧	જીએસટી રજીસ્ટ્રેશનની નકલ.
૨	પાન કાર્ડની નકલ.
૩	છેલ્લા પાંચ વર્ષમાં પુર્ણ કરેલ આ પ્રકારનાં સરકારી કામની વિગત દર્શાવતું ૩-એ પ્રમાણપત્રની નકલ સામેલ રાખવી.
૪	ટેન્ડર ફી પેટે રૂ. ૧૫૦૦.૦૦ રાષ્ટ્રીયકૃત બેંકના ડીમાન્ડ ડ્રાફ્ટ (જે ઈજારદારશ્રી દ્વારા ટેન્ડર ભરવાનું હોય તે જ ઈજારદારશ્રી દ્વારા કઢાવેલ ડી.ડી.) કાર્યપાલક ઈજનેર, જામનગર (મા×મ) વિભાગ, જામનગરના નામનો રજુ કરવાનો રહેશે.
૫	સદર કામમાં બાનામુકિત પ્રમાણપત્ર માન્ય રહેશે નહિં. રૂ. ૫.૦૦ લાખની રાષ્ટ્રીયકૃત બેંકની એફ.ડી.આર. ઓછામાં ઓછી ૬ માસની કાર્યપાલક ઈજનેર, જામનગર (મા×મ) વિભાગ, જામનગરના નામે ખોલ કરવાની રહેશે. ૬(છ) માસથી ઓછા સમયની બાનાની રકમ સ્વિકારવાપાત્ર રહેશે નહીં. આ કામ માટે બાનાની રકમને સીક્યુરીટી ડીપોઝીટ તરીકે તબદીલ કરવામાં આવશે.
૬	ઈજારદારનો વર્ગ કક્ષા—''બી'' તથા ખાસ કક્ષા—૩ (રોડ) અને ઉપરના
૭	ડ્રમ મીક્ષ પ્લાન્ટનું અઘતન સર્ટીફિકેટ રજુ કરવાનું રહેશે.
૮	રૂ. ૩૫,૦૦,૦૦૦/- ની તા.૦૧/૦૧/૨૦૨૬ કે એના પછી ઈસ્યુ થયેલ રાષ્ટ્રીયકૃત બેંકની કે સરકાર માન્ય શીડ્યુલ બેંકની બેંક સોલવંશી સર્ટીફિકેટની નકલ મોકલવાની રહેશે.

નોંધ :— ઉપરોક્ત તમામ દસ્તાવેજો ઓન લાઈન સ્કેન કરી ફરજીયાત મુકવાના રહેશે, તેમજ ઓન લાઈન મુકેલ તમામ દસ્તાવેજો પ્રિ કવોલીફિકેશન ખોલવાની તારીખથી ૭ દિવસમાં આર.પી.એ.ડી.થી અત્રેની કચેરીમાં રજુ કરવાનાં રહેશે. જો તેમ કરવામાં નિષ્ફળ જાય તો અને ઉપરોક્ત તમામ દસ્તાવેજો ઓનલાઈન સ્કેન કર્યા સિવાયનાં ટેન્ડર ગણતરીમાં લેવામાં આવશે નહીં, જેને રદ બાતલ ગણવામાં આવશે. જેની ખાસ નોંધ લેશો. આ કામની પુર્વ પાત્રતા પ્રિ કવોલીફિકેશનમાં સફળ થયેલ ઈજારદારના ભાવપત્રકો (પ્રાઈસબીડ) ખોલવામાં આવશે. પુર્વ પાત્રતા અંગેનો આખરી નિર્ણય કમીટી / સક્ષમ અધિકારીશ્રીનો અબાધિત રહેશે.

ઠેકેદારશ્રીની સહી

કાર્યપાલક ઈજનેર
જામનગર (મા×મ) વિભાગ
જામનગર.