

AHMEDABAD MUNICIPAL CORPORATION					
ABSTRACT FORM					
<b>Name of work:-Providing and Fixing 12 mtr high ventilation column on Existing Drainage line in various locations in South west zone.</b>					
Sr No.	Quantity	Item Description	Rate in Rs.	Per	Amount
1		Providing & erecting C.I and MS Ventilating columns 15 cms dia. With C.I. ornamental cap and Min. 12.00 mtr Height base fixed firm with necessary foundation with one coat of red lead oxide paint and two coat of any approved colour with 15 cms. dia 10 mt in lenght with 0.35 mt dia mt x M100 CC. encasing, NP-3 RCC Pipe 150 mm dia connection with M.H. including excavation and jointing as required etc. Complete. As per drawing ( GWSSB			
a	72.00	For 12 mt height (2mtr CI and 10m MS)	41230.00	Nos	2968560.00