

Name Of Work :- "8443-Civil Deposit Work Part-III" Repairing, Renovation & Furniture Work in Irrigation Circle Office At Sector-16, Gandhinagar

SPECIFICATION INDEX

Sr. No	ITEM DESCRIPTION	Item No. As Per G.T.S. Booklet (Building.)	Remarks
1	2	3	4
1	Dismantling doors, windows, ventilators etc. (wood or steel) shutters including chowkhats architraves, holdfasts and other attachment etc. complete and stacking them within all lead and lift.(i) Not exceeding 3 Sq.M. in area.	20.49 (i)	
2	Dismantling sanitary fittings like wash basin . W.C. pan Indian and European type, flushing tank etc. including stacking the materials with all lead and lift.	20.00	
3	Removing and scraping of old deteriorated plaster of any thickness from wall / R.C.C member including stacking of serviceable material and disposal of unserviceable from site of work with all lead and lift	As Per Separate Sheet Attached	
4	Dismantling tiled of stone floors laid in mortar including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift.	20.23	
5	Dismantling Existing Ceiling including distempering and stacking the materials with all lead and lift.	As Per Separate Sheet Attached	
6	Dismantling Existing Ply Partition including distempering and stacking the materials with all lead and lift.	As Per Separate Sheet Attached	

Name Of Work :- "8443-Civil Deposit Work Part-III" Repairing, Renovation & Furniture Work in Irrigation Circle Office At Sector-16, Gandhinagar

SPECIFICATION INDEX

Sr. No	ITEM DESCRIPTION	Item No. As Per G.T.S. Booklet (Building.)	Remarks
7	Applying general insecticide pest control treatment to floors, cupboards etc including labour materials etc. By drilling in existing floors and pour pest control solution in it and filled it with cement slury complete. Using Imidacloprid 30.5 SCas Per IS 6313 part -II(0.075% concentration by mass) or terminator (Pidilite) or equivalent is recommended 10.5ml chemical diluted with 5 liters of water application 0.5 litre chemical /Sqm of surface is recommended as per I.S	As Per Separate Sheet Attached	
8	Providing 10mm thick cement plaster in single coat on Ceiling for interior plastering upto floor two level and finished even and smooth in (i)Cement mortar 1:3 (1-cement:3-sand) (133.96+25.80)	17.58 (i)+17.91	
9	Providing 10mm thick cement plaster in single coat on brick/concrete walls for interior plastering upto floor two level and finished even and smooth in (i)Cement mortar 1:3 (1-cement:3-sand)	17.58 (i)	
10	20mm thick sand faced cement plaster on walls upto height 10 metres above ground level consisting of 12mm thick backing coat of C.M. 1:3 (1-cement : 3-sand) and 8mm thick finishing coat of C.M. 1:1 (1-cement : 1-sand) etc. complete.	17.95	

Name Of Work :- "8443-Civil Deposit Work Part-III" Repairing, Renovation & Furniture Work in Irrigation Circle Office At Sector-16, Gandhinagar

SPECIFICATION INDEX

Sr. No	ITEM DESCRIPTION	Item No. As Per G.T.S. Booklet (Building.)	Remarks
11	Applying two coats of putty & two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth.	As Per Separate Sheet Attached	
12	Ceiling painting (two coats) with plastic emulsion paint of approved brand and manufacture on undecorated ceiling surface to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth.(82.36+5.63)	As Per Separate Sheet Attached	
13	Wall painting (two coats) with plastic emulsion paint of approved brand and manufacture on undecorated wall surface to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth.	As Per Separate Sheet Attached	
14	Finishing wall with weather proof exterior emulsion paint on wall surface (two coats) to give an required shape even shade after thoroughly brushing the surface to remove all dirt, and remains of loose powdered materials.etc complete	As Per Separate Sheet Attached	

Name Of Work :- "8443-Civil Deposit Work Part-III" Repairing, Renovation & Furniture Work in Irrigation Circle Office At Sector-16, Gandhinagar

SPECIFICATION INDEX

Sr. No	ITEM DESCRIPTION	Item No. As Per G.T.S. Booklet (Building.)	Remarks
15	P & L 24" x 24" vitrified 8 mm thick tile flooring over 20 mm (average) base of cement mortar 1:6 (1 cement: 6 coarse sand) on new surface or fixing on existing flooring by adhesive material including dismantling of existing flooring and jointed with color cement slurry including finised with flush pointing & cleaning the surface etc. complete for antiskit	14.43 (A)	Use 600 x 600 x 6-8 mm Vitrified Tiles Instead Of 25mm Thick Kota Stone Slab
16	Providing and laying coloured glazed tiles of the size 300 mm x 200 mm x 8 mm / 300 mm x 450 mm x 8 mm in skirting, risers of steps and dedo on 10 mm. thick cement plaster 1:3 (1 cement : 3 coarse sand) & jointed with white cement slurry.	14.32	Use 300 x 450 x 6-8 mm Glazed Tile in skirting, risers of steps and dedo Instead Of 6mm Thick White Glazed Tile
17	P & L 600 x 1200 vitrified 6-8 mm thick tile flooring over 20 mm (average) base of cement mortar 1:6 (1 cement: 6 coarse sand) on new surface or fixing on existing flooring by adhesive material including dismantling of existing flooring and jointed with color cement slurry including finised with flush pointing & cleaning the surface etc. complete for Any shade	14.43 (A)	Use 600 x 1200 x 6-8 mm Vitrified Tiles Instead Of 25mm Thick Kota Stone Slab

Name Of Work :- "8443-Civil Deposit Work Part-III" Repairing, Renovation & Furniture Work in Irrigation Circle Office At Sector-16, Gandhinagar

SPECIFICATION INDEX

Sr. No	ITEM DESCRIPTION	Item No. As Per G.T.S. Booklet (Building.)	Remarks
18	Providing and laying 600 x 1200 mm tiles of 1st quality of Any brand of 6 to 8 mm. thick in skirting, risers of step and dedo on a bed of 10 mm. thick cement mortar 1:3 (1 cement : 3 coarse sand) including pointing & cleaning the surface etc. complete. as Approved And directed by EIC.	14.32	Use 600 x 1200 x 6-8 mm Vitrified Tile in skirting, risers of steps and dedo Instead Of 6mm Thick White Glazed Tile
19	Applying priming coat and Painting two coats on new or previously painted steel and other metal surface with enamel paint, brushing, interior to give an even shade including cleaning the surface an even shade including cleanicn the surface of all dirt, dust and other foreign matter.(=36.06+91.29)	19.11+19.2	
20	Providing & Placing in position Plywood Partition 75mm Thick with 1mm thick Outside laminate finish & Inside 6mm Thick mdf (Water Proof MDF) with PU Finish With 4 x 4mm Design Groove as/Architect Design, Stucture made from 50 x 25 x 2.3 mm alluminium Section and Both Side in 12mm BWP plywood of standard make like Century, Greenlam, Marine, Greenply, Saint-Gobain, Sainik etc, with edge finish in teakwood batten & Melamine Polish on Batten Patti etc. complte,with all necessary tools & Accesories etc. complete. as per instruction given by engineer in charge/Architect.	As Per Separate Sheet Attached	

Name Of Work :- "8443-Civil Deposit Work Part-III" Repairing, Renovation & Furniture Work in Irrigation Circle Office At Sector-16, Gandhinagar

SPECIFICATION INDEX

Sr. No	ITEM DESCRIPTION	Item No. As Per G.T.S. Booklet (Building.)	Remarks
21	Providing & Placing in position Charcoal Fluted Panel 19mm Thick as/Architect Design,Fixing on ply partition with all necessary tools & Accesories etc. complete. as per instruction given by engineer in charge/Architect.	As Per Separate Sheet Attached	
22	Providing & Placing in position modesty(privacy) panel of size 1675 X 1220 mm or 1700 x 1220 mm or as per requirement having 1mm thick laminate finish Both side, Modestry(privacy) Panel made from 19mm (2 Layer=38mm) BWP plywood of standard make like Century, Greenlam, Marine, Greenply, Saint-Gobain, Sainik etc, with edge finish in teakwood batten & Melamine Polish on Batten Patti etc. complte,with all necessary tools & Accesories etc. complete as per instruction given by engineer in charge/Architect.	As Per Separate Sheet Attached	
23	Providing & Placing in position table of size 2440 X 900 X 750 mm with 1mm thick laminate finish outer side & Inside 0.8mm thick inner laminate Finish, Top & Side made from 19mm (2 Layer=38mm) BWP plywood of standard make like Century, Greenlam, Marine, Greenply, Saint-Gobain, Sainik etc, with edge finish in teakwood batten & Melamine Polish on Batten Patti etc. complte,with all necessary tools & Accesories etc. complete.After Finishing 18mm Italian Marble with all Finishing need to be provided as Top & With Chamfer Edges as per instruction given by engineer in charge/Architect.	As Per Separate Sheet Attached	

Name Of Work :- "8443-Civil Deposit Work Part-III" Repairing, Renovation & Furniture Work in Irrigation Circle Office At Sector-16, Gandhinagar

SPECIFICATION INDEX

Sr. No	ITEM DESCRIPTION	Item No. As Per G.T.S. Booklet (Building.)	Remarks
24	Providing & Placing in position Low Height Storage of size 900 X 450 X 765 mm with 1mm thick laminate finish outer side & Inside 0.8mm thick inner laminate Finish, Top,Bottom,Shelf & Both Side & Shutter made from 19mm BWP plywood & back side in 12mm BWP plywood of standard make like Century, Greenlam, Marine, Greenply, Saint-Gobain, Sainik etc,Drawer & Sliding Shutter with edge finish in teakwood batten & Melamine Polish on Batten Patti etc. complte,with all necessary tools & Accesories etc. complete. as per instruction given by engineer in charge/Architect.	As Per Separate Sheet Attached	
25	Providing & Placing in position Plywood Partition 75mm Thick with 1mm thick Both side laminate finish With 4 x 4mm Design Groove as/Architect Design and Plain/Frosted Film 8mm Toughen glass in Middle of partition with both side finish in teakwood batten & Melamine Polish on Batten Patti etc, Stucture made from 50 x 25 x 2.3 mm alluminium Section and Both Side in 12mm BWP plywood of standard make like Century, Greenlam, Marine, Greenply, Saint-Gobain, Sainik etc, with edge finish in teakwood batten & Melamine Polish on Batten Patti etc. complte,with all necessary tools & Accesories etc. complete. as per instruction given by engineer in charge/Architect.	As Per Separate Sheet Attached	

Name Of Work :- "8443-Civil Deposit Work Part-III" Repairing, Renovation & Furniture Work in Irrigation Circle Office At Sector-16, Gandhinagar

SPECIFICATION INDEX

Sr. No	ITEM DESCRIPTION	Item No. As Per G.T.S. Booklet (Building.)	Remarks
26	Providing & Placing in position Plywood Partition 75mm Thick with 1mm thick Both side laminate finish With 4 x 4mm Design Groove as/Architect Design, Stucture made from 50 x 25 x 2.3 mm alluminium Section and Both Side in 12mm BWP plywood of standard make like Century, Greenlam, Marine, Greenply, Saint-Gobain, Sainik etc, with edge finish in teakwood batten & Melamine Polish on Batten Patti etc. complte,with all necessary tools & Accesories etc. complete. as per instruction given by engineer in charge/Architect.	As Per Separate Sheet Attached	
27	Providing & Placing in position table of size 1675 X 800 X 750 mm or size 2135 X 900 X 75 with 1mm thick laminate finish outer side & Inside 0.8mm thick inner laminate Finish, Top & Side BWP plywood of standard make like Century, Greenlam, Marine, Greenply, Saint-Gobain, Sainik etc, with edge finish in teakwood batten & Melamine Polish on Batten Patti etc. complte,with all necessary tools & Accesories etc. complete.After Finishing 8mm Toughen Glass with chamfer Edge need to be provided as Top as per instruction given by engineer in charge/Architect.	As Per Separate Sheet Attached	

Name Of Work :- "8443-Civil Deposit Work Part-III" Repairing, Renovation & Furniture Work in Irrigation Circle Office At Sector-16, Gandhinagar

SPECIFICATION INDEX

Sr. No	ITEM DESCRIPTION	Item No. As Per G.T.S. Booklet (Building.)	Remarks
28	Providing & Placing in position Operable Shutter Wardrobe of size 1220 X 450 X 2440 mm with 1mm thick laminate finish outer side & Inside 0.8mm thick inner laminate Finish, Top,Bottom,Shelf & Both Side & Shutter made from 19mm BWP plywood & back side in 12mm BWP plywood of standard make like Century, Greenlam, Marine, Greenply, Saint-Gobain, Sainik etc, with edge finish in teakwood batten & Melamine Polish on Batten Patti etc. complete,with all necessary tools & Accesories etc. complete. as per <u>instruction given by engineer in charge/Architect.</u>	As Per Separate Sheet Attached	
29	Providing Decorative Center Table/Coffe Table size of 0.45 m x 0.75 m x 0.45 m as directed by Engineer-in-charge with all necessary tools & Accesories etc. complete.	As Per Separate Sheet Attached	
30	Providing Modern Sofa Length as per requirement (m) x 0.8m x 0.8m as Shown in architecture images using plywood Structure in frame & legs in m.s powder coating,Standrad Foam Sheet To be Used in Seating & Back Rest of Sofa 4 inch as base and 2 inch on top as soft foam Brand Like Curlon(20 year warranty on foam)for better comfort & Standrad Company Fabric All Side as directed by Architect/Engineer-in-charge with all necessary tools & Accesories etc. complete.	As Per Separate Sheet Attached	
31	Providing Modern Arabian Style curtain including Standard Fabric+Black Out in Back Side+Channel+Sweiving +Press Of Curtain+Fitting as directed by Engineer-in-charge with all necessary tools & Accesories etc. complete.	As Per Separate Sheet Attached	

Name Of Work :- "8443-Civil Deposit Work Part-III" Repairing, Renovation & Furniture Work in Irrigation Circle Office At Sector-16, Gandhinagar

SPECIFICATION INDEX

Sr. No	ITEM DESCRIPTION	Item No. As Per G.T.S. Booklet (Building.)	Remarks
32	Providing and fixing in position 150 mm high, English letters made from 1.5 mm thick stainless steel Plate (500mm x 175mm) sheet as directed by Engineer-in-charge with all necessary tools & plants etc. complete. As directed by engineer in charge	As Per Separate Sheet Attached	
33	Providing and fixing 35mm flush door shutters solid core construction with frame of 1st class teak wood with cross bend and face veneer of plywood face pannels including anodized alluminium butt hinges with necessary serews, Allu. Aldrop, Allu. Handle 6", Allu. Tadi 10", Allu. Stopper 8", Allu. Rubber Plug.& Door Closer [B] Decorative type with 1mm laminated sheet on both sides & block board core anodized alluminium butt hinges.[C] Vision Panel Size of 380 mm X 1070 mm with 8mm Toughen Glass With Batten Patti Both Side [C] Flush door shutters 35 mm thick including oil paint etc. with all necessary fixtures complete.As Directed & Approved By EIC.	As Per Separate Sheet Attached	
34	Providing and fixing Zebra blind roller curtain with superior quality Acmeda Mechanism including all necessities fitting like breaket chain etc. complete as per instruciton of Engineer in charge. Make as per tender or equivalent.	As Per Separate Sheet Attached	

Name Of Work :- "8443-Civil Deposit Work Part-III" Repairing, Renovation & Furniture Work in Irrigation Circle Office At Sector-16, Gandhinagar

SPECIFICATION INDEX

Sr. No	ITEM DESCRIPTION	Item No. As Per G.T.S. Booklet (Building.)	Remarks
35	Providing & Placing in position Outside Main Board Made from base 18mm BWP plywood of standard make like Century, Greenlam, Marine, Greenply, Saint-Gobain, Sainik etc, and Finish With Stainless Steel Plate of size 1220 X 2440 mm 1.5mm thick Front side, with edge finish in teakwood batten & Melamine Polish on Batten Patti etc. complete, with all necessary tools & Accesories etc. complete as per instruction given by engineer in charge/Architect.	As Per Separate Sheet Attached	
36	Providing & Fixing Flase Ceiling of Aerolight light weight calcium silicate tiles Tegular Edge of Size 595 x 595 x 15mm densified edge, having 100% humidity resistance and incombustible as per BS 476 Part -4 with thermal conductivity of 0.043 W/m0 kC, with NRC of 50 and approved surface design to be placed in the grid suspended ceiling with border of gypsum sheet. Grid system made of Galvanised steel section with main "T" runner 3.6 mt long with size 38 x 24 x 0.30 mm spaced at 1200 mm c/c and cross "T" of 1.2 mt long with size 24 x 24 x 0.30 mm spaced between main "T" at 600 mm c/cto form a grod of 600 x 1200 mm and secondary cross "T" of length 600 mm to be inter locked at middle of the 600 x 1200 mm panel to be fixed all around the perimeter of the wall. The main "T" runner to be suspended from the ceiling using GI sloted cleats and 50 mm long dash fastners, 4 mm GI adjustable rods with galvanised level clips with all labour and material and as directed by Engineer Incharge	As Per Separate Sheet Attached	

Name Of Work :- "8443-Civil Deposit Work Part-III" Repairing, Renovation & Furniture Work in Irrigation Circle Office At Sector-16, Gandhinagar

SPECIFICATION INDEX

Sr. No	ITEM DESCRIPTION	Item No. As Per G.T.S. Booklet (Building.)	Remarks
37	Providing and fixing star white wall mounted water closet squatting pan (European type W.C. Pan) CERA Wall hung EWC with soft close seat cover with integral 'p' or 'S' trap including jointing the trap with C. I.soil pipe in C.M. 1:1 including seat cover with C.I Chair Brackets fittings etc. complete including labour charge and directed as per EIC	As Per Separate Sheet Attached	
38	Providing and fixing Health Faucet ABS with Rubbit Cleaning System (CERA), 1.25 m Long PVC Flexible Tube & ABS Wall Hooks with 15 mm dia with center point with Extension nipple, labour charge, etc as per EIC.	As Per Separate Sheet Attached	
39	Providing and fixing window having extruded aluminum Colour anodized section frame main outer size 63.50 x 38.10 x 1.95 mm,@ Wt 1.094 Kg / Rmt, horizontal two track member size 61.85 mm x 31.75 mm x 1.20mm @ wt.of 0.695 Kg/mt, vertical member of size 61.85 mm x 31.75mm x 1.30 mm @ wt.of 0.659 Kg/mt with sliding shutters of horizontal member size 40mm x 18mm x 1.29mm @ wt.of 0.456Kg/mt, vertical member of size 40mm x 18mm x 1.29mm @ wt.of 0.456Kg/mt, @ Wt. 0.457 Kg/mt with 5 mm thick transparent bronze colour tinted float glass with powder coated aluminum fittings and fixtures and transparent silicon sealant glass fixing to frame as per details etc complete for window.	As Per Separate Sheet Attached	

Name Of Work :- "8443-Civil Deposit Work Part-III" Repairing, Renovation & Furniture Work in Irrigation Circle Office At Sector-16, Gandhinagar

SPECIFICATION INDEX

Sr. No	ITEM DESCRIPTION	Item No. As Per G.T.S. Booklet (Building.)	Remarks
40	Providing and laying 16-18 mm thick polished Black Granite stone slab machine cut in single piece in sill and jambs laid on 20 mm thick cement mortar 1 : 3 (1 cement : 3 coarse sand) with half round Edge Moulding laid over and jointed with grey cement slurry incl. rubbing and polishing etc complete.as per EIC	As Per Separate Sheet Attached	
41	Pro. And fixing single layer water proof gypsum board 12.5 mm thick sections using water proof board of size 1220 mm x 1830 mm x 8.0 mm suspended by GI suspender channel of size 25 mm x 3 mm with intermediate channel of size 18 mm x 40 mm x 0.8 mm at 1220 mm center to center ceiling section of size 40 mm x 35 mm x 0.55 mm at 457 mm c/c and perimeter channel A of size 20 mm x 27 mm x 30 mm x 0.5 mm at edges & drops incl.paper tap sand soffit cleat, anchor fastener, scotch bolt connecting cleat,joining compound top coat on ceiling incl.making necy.opening for light fitting,diffuser etc. comp. as per detail drawing as directed	As Per Separate Sheet Attached	

**Deputy Executive Engineer
Capital Project Sub Div. No.03
Gandhinagar**

**Executive Engineer
Capital Project Division No.1
Gandhinagar**