

Name of work: - 2215 Water Supply & Sanitation.

- (107) Gandhinagar Sewage Scheme.

Cleaning/ Removing choking of Manholes, Chambers/ C.W.C, Strom/ Drainage lines and desilting the same if required with labours, Mechanical Bucket/ Hand bucket, lari & other tools (i.e. Trikam, Pavda, Rassa, Battery, G.T. Salia, Safety Tools etc.) with disposing silt as shown places under Drainage Inquiry Sector No.22, In G.T.S. Nothing extra to be paid for any insurance or depreciation of tools etc. (Rate is for 8 hour shift with minimum 8 complains to be solved. Minimum 3 labours with mukadam to be provided.) or in case of pollution/ pre- monsoon action plan/ drainage desilting work / min 10 Nos. of MH or chamber Should be Desilted or as per instruction by EIC.)

SPECIFICATION

Item No.1

Cleaning/ Removing choking of Manholes, Chambers/ C.W.C, Strom/ Drainage lines and desilting the same if required with labours, Mechanical Bucket/ Hand bucket, lari & other tools (i.e. Trikam, Pavda, Rassa, Battery, G.T. Salia, Safety Tools etc.) with disposing silt as shown places under Drainage Inquiry Sector No.22, In G.T.S. Nothing extra to be paid for any insurance or depreciation of tools etc. (Rate is for 8 hour shift with minimum 8 complains to be solved. Minimum 3 labours with mukadam to be provided.) or in case of pollution/ pre- monsoon action plan/ drainage desilting work / min 10 Nos. of MH or chamber Should be Desilted or as per instruction by EIC.)

Materials and equipments required for dismantling of dummies, such as wire rope, bucket, chiseling, workers etc. shall be brought by contractor.

- 1) The contractor shall have to remove all tree leaves, brick bats, polyethylene bags, paper bags, sand, earth and other foreign material from the existing catch water chamber of any depth including all under ground lift and the cleaned debris shall be thrown away 50 m. from the Manholes Chamber/ C.W.C. (Catch water chamber)
- 2) During the work of execution it is possible that gas may come up and may do any injury to the labour or the other person working on site. The contractor shall have to keep all safety belts artificial respirator system. Oxygen gas mask, suitable vehicle etc. to safeguard and protect any worker. He shall have to take every or precaution against any such happenings any accident that may occur during the removal of site from the mines or manholes of any depth. He will be totally responsible for such happening and he shall have to make good the damage done at the properly in any way or compensation the amount to in jury done any person will ever the cost may be. In no case state Govt. or any officer will be held responsible for such type of mistake or fatal accident. No compensation or any extra payment will be given to him for such happenings.
- 3) The contractor has to prepare the stacks of wastes as directed by Engineer in charge or shall have to throw away in nearly pit as directed within 50 m. lead from Manholes Chamber/ catch water chamber.

4) The contractor shall have to make proper provision for protection work by providing rope, fencing and lightening and height or other safety boards or sign boards to avoid accidents to vehicles or persons.

5) If may be noted that for any fatal accident due to negligence of contractor, the contractor will be fully responsibility for such accident.

6) Cleaning work of Manholes Chamber/ C.W.C. is to be done by labour on No. basis as per site condition & requirement & instruction of Engineer in charge.

The payment shall be made for a unit of one No. of Manholes Chamber/ C.W.C. cleaned.

Measurements for Payment:

The rate shall be for a unit of one Number.

Dated Signature
of the Contractor

Executive Engineer,
Capital Project Division No.3,
Gandhinagar.

