

Name of Work :- Construction of Gram Panchayat office ( for Population from 5000- 10000)  
at Village Shiyalbet, Tal. Jafrabad Dist. Amreli

### Bill of Quantities

Memorandum showing items of works to be carried out

Item No.	Quantities Estimated but may be more or less.		Item of work	Estimated Rates		Unit	Total amount according to estimated
				In Figure Rs. Ps	In Words.		
1	78.200	Cum	Excavation for foundation upto 1.50 M.depth including sorting out & stacking of useful materials i.e. disposing the excavated stuff up to All lead (a) Loose or soft soil.	212.51	Rupees Two Hundred Twelve and Paise Fifty One only	One Cubic metre	16618.28
2	106.500	Cum	Excavation for foundation upto 1.50 M.depth including sorting out & stacking of useful materials i.e. disposing the excavated stuff up to All lead (a) Dense or Hard soil.	272.57	Rupees Two Hundred Seventy Two and Paise Fifty Six only	One Cubic metre	29028.70
3	20.700	Cum	Providing and laying cement concrete 1:4:8 (1 cement, 4sand, 8 Crushed stone aggregates 40 mm.Nominal size) and curing complete, excluding cost of formwork in (a) Foundation and Plinth	2927.45	Rupees Two Thousand Nine Hundred Twenty Seven and Paise Forty Five only	One Cubic metre	60598.21
4	21.600	Cum	Providing and laying ordinary cement concrete 1:1:2 (1cement, 1sand, 2 graded stone aggregates 20 mm.Nominal size) and finishing smooth with curing etc. complete excluding cost of form work and reinforcement for reinforced cement concrete work in in A) Foundations, footings, base of columns and mass concrete	7875.43	Rupees Seven Thousand Eight Hundred Seventy Five and Paise Forty Three only	One Cubic metre	170109.28
5	7.200	Cum	Providing and laying ordinary cement concrete 1:1.5:3 (1cement, 1.5sand, 3 graded stone aggregates 20 mm.Nominal size) and finishing smooth with curing etc. complete including the cost of formwork but excluding the cost of reinforcement of R.C.C. work in Column (iii) Having cross-sectional area more than 0.085 Sq.M. and up to 0.12Sq.M	10860.04	Rupees Ten Thousand Eight Hundred Sixty and Paise Four only	One Cubic metre	78192.28

6	29.000	Cum	Brickwork using common burnt clay building brick shaving crushing strength not less than 35 Kg/Sqcm. in foundation and plinth in cement mortar 1:6(1 Cement ; 6 Fine sand) Conventional bricks	4214.33	Rupees Four Thousand Two Hundred Fourteen and Paise Thirty Three only	One Cubic metre	122215.57
7	36.200	Cum	Filling in plinth with sand under floors including ramming watering, consolidating and dressing etc.complete.	481.80	Rupees Four Hundred Eighty One and Paise Eighty only	One Cubic metre	17441.16
8	120.300	Cum	Filling available excavated earth (excluding rock) in trenches plinth, sides of foundations etc. in layers not exceeding 20 cm in depth consolidating each disposed layer by ramming and watering.	136.92	Rupees One Hundred Thirty Six and Paise Ninety Two only	One Cubic metre	16471.47
9	46.000	Cum	Brickwork using common burnt clay building brick shaving crushing strength not less than 35 Kg/Sqcm. in super structure for all floors. in cement mortar 1:6(1 Cement ;6 Fine sand)	4518.37	Rupees Four Thousand Five Hundred Eighteen and Paise Thirty Seven only	One Cubic metre	207845.02
10	1.700	Cum	Providing and laying cement concrete1:1.5:3 (1cement, 1.5sand, 3 gradedstone aggregates20 mm.Nominal size) and curing complete, including cost of formwork in sill and sides (R.C.C. band) but excluding the cost of reinforcement for all Floor level.	7229.32	Rupees Seven Thousand Two Hundred Twenty Nine and Paise Thirty Two only	One Cubic metre	12289.84
11	2.800	Cum	Providing & laying ordinary C.C. 1:1 1/2:3 ( 1 cement ,1 1/2 course sand, 3 graded stone agg. of 20 mm nominal size )and for R.C.C. LINTELS incl. Finishing smooth with curring of formwork but excl. the cost of reinforcement.for above floor for all Floor level.	8904.52	Rupees Eight Thousand Nine Hundred Four and Paise Fifty Two only	One Cubic metre	24932.65

12	1.700	Cum	Providing & laying cement concrete 1:11/2:3 (1 cement ,11/2 course sand,3graded stone agg.of 20 mm nominal size) for rein-forcement concrete CHHAJJAS not exceeding 10cm. thickness for all Floor level incl. finishing the exposed surface with C.M. 1:3 (1 cement ,3 fine sand) to give a smooth and ever surface, centering, formwork and curring comp.Excl. the cost of reinforcement.above plinth for all Floor level.	7082.90	Rupees Seven Thousand Eighty Two and Paise Ninety only	One Cubic metre	12040.93
13	25.600	Cum	Providing & laying C.C. 1:11/2:3 (1 cement ,11/2 course sand,3 graded stone agg.of 20 mm nominal size) and finishing smooth with curring etc. comp. incl. the cost of formwork but excl. the cost of reinforcement for R.C.C. work in. (A) Beam :- Having cross sectional Area 0.085 to 0.12 Sqm.for all Floor level	8049.50	Rupees Eight Thousand Forty Nine and Paise Fifty only	One Cubic metre	206067.20
14	26.300	Cum	Providing & laying ordinary cement concrete1:11/2:3 (1 cement ,11/2 course sand,3 graded stone agg.of 20 mm nominal size) exposed work with curring etc.comp. incl. the cost of formwork but excluding the cost of reinforce ment for R.C.C. work in. SLAB :- having more then 10cm. and end upto 13cm. thickness.for all Floor level	7276.22	Rupees Seven Thousand Two Hundred Seventy Six and Paise Twenty Two only	One Cubic metre	191364.58
15	1.700	Cum	Providing & laying ordinary cement concrete1:11/2:3 (1 cement ,11/2 course sand,3 graded stone agg.of 20 mm nominal size) exposed work with curring etc.comp. incl. the cost of formwork but excluding the cost of reinforce ment for R.C.C. work in. Staircases Excluding Landing up to all floor	8710.80	Rupees Eight Thousand Seven Hundred Ten and Paise Eighty only	One Cubic metre	14808.36
16	11036.000	Kg	Thermo Mechanically treated bar F.F.415 Steel reinforcement for R.C.C. work including bending, binding and placing in position complete for all Floor level.	68.68	Rupees Sixty Eight and Paise Sixty Eight only	One Kilogram	757952.48

17	11.500	Sqm	Providing fixing of Polished Kotah stone frame for Doors & wIndows of 15cmx4 cm. Size including necessary holdfasts, holes for fixtures and fastenings incl. all labour & materials etc. comp	972.06	Rupees Nine Hundred Seventy Two and Paise Six only	One Squere metre	11178.69
18	10.700	Sqm	Providing and fixing 35mm. Thick Panelled,glazed orPanelled and glazed shutters for doors,windows andclearstory windows including anodised alluminiumbutt hinges with necessary screws and Indian TeakWood shutters with-(B) Partical board panells.12mm. thick including applying primer and two coats of oil painting etc. complete	3933.51	Rupees Three Thousand Nine Hundred Thirty Three and Paise Fifty One only	One Squere metre	42088.55
19	287.000	Sqm	Providing 15mmthick cement plaster in single coat on fair side of Brick/concrete walls for interior plastering for all floor and finished even and smooth in (I)cement mortar 1:3 (1 cement:3 sand) .for all floor.	206.91	Rupees Two Hundred Six and Paise Ninety One only	One Squere metre	59383.17
20	464.000	Sqm	Providing 10 mmthick cement plaster in single coat on fair side of Brick/concrete walls for interior plastering for all floor and finished even and smooth in (I)cement mortar 1:3 (1 cement:3 sand) .for all Floor level finished even & Smooth with floating coat of neat cement slurry.	207.61	Rupees Two Hundred Seven and Paise Sixty One only	One Squere metre	96331.04
21	137.900	Sqm	Providing and laying 24" x 24" vitrified 8MM thick tile flooring over 20MM (average) base of cement mortar 1:6 (1- Cement : 6- Coarse Sand) on new surface or fixing on existing flooring by adhesive material including dismentalling of existing flooring and jointed with colour cement slurry including finished with flush pointing and cleaning the surface etc. complete. For Light shade	1264.41	Rupees One Thousand Two Hundred Sixty Four and Paise Forty One only	One Squere metre	174362.13

22	11.400	Sqm	Providing and laying Ceramic tiles 6mm thick in flooring treads of steps and landing laid on a bed of 12mm thick cement mortar 1:3 (1-cement : 3-coarse sand ) finishing with flush pointing in white cement	992.15	Rupees Nine Hundred Ninety Two and Paise Fifteen only	One Squire metre	11310.51
23	50.600	Sqm	Providing and laying Ceramic tiles 6mm thick in skirting risers of steps and dedo on 10mm thick cement plaster 1:3 (1-cement : 3-coarse sand) and jointed with white cement slurry	1023.88	Rupees One Thousand Twenty Three and Paise Eighty Eight only	One Squire metre	51808.32
24	311.000	Sqm	Finishing wall with weather proof exterior emulsion paint on wall surface(two coats) to give an required shape even shade after thoroughly brushing the surface to remove all dirt, and remains of loose powdered materials etc complete	120.26	Rupees One Hundred Twenty and Paise Twenty Six only	One Squire metre	37400.86
25	480.000	Sqm	Distempering (Two coats) with oil bound distemper of approved brand and manufacture and of required shade on wall surface to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar dropping and other foreign matter and also including preparing the surface even and papered smooth	75.68	Rupees Seventy Five and Paise Sixty Eight only	One Squire metre	36326.40
26	3.000	No	Providing and fixing water closet squatting pan (Indian type W.C.Pan) size 580 mm. incl. 100mm. Size P trap & Foot rest(Earthwork, bed concrete,foot rests and trap to be measured and paid for separately) (A) Vitreous china (I) Long pattern white colour.	1436.33	Rupees One Thousand Four Hundred Thirty Six and Paise Thirty Three only	One Number	4308.99
27	3.000	No	Providing and fixing PVC SWR Nahni trap IS 14735 for drain - 100 mm diameter with jali of the following nominal diameter of self cleansing design with C.I screed down or hinged grating including the cost of cutting and making good the walls.	586.27	Rupees Five Hundred Eighty Six and Paise Twenty Seven only	One Number	1758.81

28	15.000	Rm	Proving and fixing cast iron spigot and socket soil, waste and ventilating pipes of the following nominal size.(C) 100 mm. Dia.	892.39	Rupees Eight Hundred Ninety Two and Paise Thirty Nine only	One Running metre	13385.85
29	1.000	No	Proving and fixing in position cowl vent to pipes(C) 100 mm. Dia.	505.17	Rupees Five Hundred Five and Paise Seventeen only	One Number	505.17
30	3.000	No	Providing and fixing S.W. gully trap with C.I. grating brick masonry chamber and water tight C.I. cover with frame of 300mm x 300mm size (inside) with standard weight.(i) Square mouth traps. (A) 100mm x 100mm size P type.	1292.19	Rupees One Thousand Two Hundred Ninety Two and Paise Nineteen only	One Number	3876.57
31	2.000	No	Providing and fixing urinal of approved quality including connection with trap and with integral longitudinal flush pipe (A) White earthen ware flat back or corner type size 430mm x 260mm x 350mm	1074.86	Rupees One Thousand Seventy Four and Paise Eighty Six only	One Number	2149.72
32	1.000	No	Constructing brick masonry road gully chamber 450mm x 450mm x 775mm with vertical grating complete With C.I. Manhole Cover 450x600 mm size	3504.02	Rupees Three Thousand Five Hundred Four and Paise Two only	One Number	3504.02
33	2.000	No	Providing and fixing wash basin with single hole for pillar tape with C.I. of M.S. brackets painted white including cutting holes and making good the same but excluding fittings (A) Stainless steel Acrysil or Equivalent make- Flat back wash basin 550mm x 400mm size with CP brass couplin, padastal matching the shade, waste pipe etc comp	1970.39	Rupees One Thousand Nine Hundred Seventy and Paise Thirty Nine only	One Number	3940.78

34	45.000	Rm	Providing, laying and jointing in true line and level 110 diameter U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 110 mm diameter x 149 mm length x 145 mm heigh at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	876.90	Rupees Eight Hundred Seventy Six and Paise Ninety only	One Running metre	39460.50
35	35.000	Rm	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [D] 32mm.	338.24	Rupees Three Hundred Thirty Eight and Paise Twenty Four only	One Running metre	11838.40
36	30.000	Rm	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [B] 20mm.	208.80	Rupees Two Hundred Eight and Paise Eighty only	One Running metre	6264.00
37	5.000	No	Proving and fixing screw down bib taps of following size.(A) Brass screw downbib tap polished bright. (I) 15 mm. Dia.	186.83	Rupees One Hundred Eighty Six and Paise Eighty Three only	One Number	934.15

38	1.000	No	Providing sock pit of 5.0 Cumt. Volume including excavating and filling brick bats with dry masonry work at top for 45 cm. Height including covering the top with stone including providing vatas in c.m. 1:3 with finishing, curing etc. complete as directed.	3457.27	Rupees Three Thousand Four Hundred Fifty Seven and Paise Twenty Seven only	One Number	3457.27
39	500.000	Lit	Providing and Fixing double coated Syntex or Equivalent PVC ( ISI) mark water tank of required capacity each with all necessary fittings and connection etc. comp on terrace or as directed by Engineer - in- charge.	3.95	Rupees Three and Paise Ninety Five only	One Litre	1975.00
40	81.000	Sqm	Providing and laying broken china mosaic flooring for terrace using 12 mm to 20 mm broken pieces of glazed tiles to be laid over cement mortar 1:3 to plain or slope and to be tempered to bring mortar creme out upto surface using white cement including rounding off junctions and extending them upto 15 cm along the wall, clearing with water and oxalic acid etc. as directed.	779.70	Rupees Seven Hundred Seventy Nine and Paise Seventy only	One Squere metre	63155.70
41	21.100	Sqm	Pro. /Fix. with windows with 40x40x5mm. Iron angle & frame 30x30x4 mm size in Double Shutter with B.G. 20 Gauge Sheet plates with , Hold fasts ,Iron hinges handles, stopper ,and locking arrangement etc. comp. Steel welded is built up section cutting hoisting , finishing in two coats of oil painting over coat of primer coat etc. comp.	3930.67	Rupees Three Thousand Nine Hundred Thirty and Paise Sixty Seven only	One Squere metre	82937.13
42	598.000	Kg	Providing and fixing M.S. Grills of required pattern to wooden frames of Pipe / Angles etc. including Priming coat of approved primer and Two coats of Oil painting etc. complete Ordinary grill	172.41	Rupees One Hundred Seventy Two and Paise Forty One only	One Kilogram	103101.18



43	11.300	Sqm	Providing and laying polished kota stone slab flooring over 20mm (average) thick base of cement mortar 1:6 (1 cement : 6 coarse sand) or L.M. 1:1.5 laid and jointed with grey cement slurry including rubbing and polishing etc. complete 25mm Thick	1019.39	Rupees One Thousand Nineteen and Paise Thirty Nine only	One Square metre	11519.10
44	7.900	Sqm	Providing and fixing 30mm thick FACTORY MADE SOLID PANEL PVC DOOR SHUTTER consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19mm x 19mm for stiles and 15mm x 15 mm for top and bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture, M.S. frame shall be covered with 5 mm thick heat moulded PVC 'C' channel of size 30 x 50 mm forming stiles, and 5mm thick 75mm wide PVC sheets for top rail, lock rail and bottom rail on either side, and 10mm (5mm x 2) thick, 20mm wide cross PVC sheet as gap insert for top rail and bottom rail, Panelling of 5 stiles and rails with 30mm wide x 5mm thick PVC sheet beading on either side, and joined together with solvent cement adhesive,. An additional 5mm thick PVC strip of 20mm width is to be stulk on the interior side of the 'c' channel using PVC solvent cement adhesive etc. complete as per direction of Engineer in charge, manufacture's specification and drawing.	1146.36	Rupees One Thousand One Hundred Forty Six and Paise Thirty Six only	One Square metre	9056.24
45	1.200	Sqm	Providing & Fixing Acrylic sheet name board size 2.00 mt x 0.60 sqm. With painting letters Indicating Gram panchayat office / Village/ Taluka/ Dist. Etc. as directed by Adm. Department etc. with all required material & Labour comp.	1515.00	Rupees One Thousand Five Hundred Fifteen and Paise Zero only	One Square metre	1818.00
46	2.000	No	Providing & Fixing 4.50 Kg Co2 type Fire Extinguisher with all required equipment & Labour comp.	5555.00	Rupees Five Thousand Five Hundred Fifty Five and Paise Zero only	One Number	11110.00
47	4.000	No	Providing & Fixing 6.00 Kg ABC type Fire Extinguisher with all required equipment & Labour comp.	2525.00	Rupees Two Thousand Five Hundred Twenty Five and Paise Zero only	One Number	10100.00

48	12.000	Point	Point wiring for Light / Bell with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in/ on surface on wall/ceiling complete with 6A Modular type switch / bell push & accessories and earth continuity of following type, erected on PVC / Metallic box, single mounting base frame covered with textured/metallic front plate modules erected on / in wall / ceiling as per pipe erected, with necessary Lamp holder/ceiling rose / H.D.Connector as directed. (f) with medium class Rigid PVC pipe and accessories Cat- III	449.45	Rupees Four Hundred Forty Nine and Paise Forty Five only	One Point	5393.40
49	6.000	Point	Point wiring for FAN with 2-1.5 sq.mm & earthwire of 1.5 sq.mm (Green) both are of .ISI marked 1.1 KV Grade FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / flushed on wall/ceiling complete with 6A Modular type switch and hum free EME four or more step type electronic fan regulator with separately mounted and accessories with earth continuity of following type erected on PVC / Metallic box, single mounting base frame covered with textured/metallic front plate modules erected on / in wall / ceiling as per pipe erected. with necessary ceiling rose / H.D.Connector as directed. (f) with medium class Rigid PVC pipe and accessories Cat- III	629.23	Rupees Six Hundred Twenty Nine and Paise Twenty Three only	One Point	3775.38
50	4.000	Point	Point wiring for Looped Plug with 6A Modular type switch & 5 pin socket erected on PVC / Metallic box, single mounting base frame covered with textured / metallic front plate modules erected on / in wall / ceiling with following type accessories Cat-III	241.39	Rupees Two Hundred Forty One and Paise Thirty Nine only	One Point	965.56
51	2.000	Point	Point wiring for individual Plug with & Earth wire of FRLS PVC insulated multistrand copper wires, in following type of pipe to be erected concealed in / surface of wall/ceiling complete with Modular type switch and 5 Pin plug erected on PVC/ Metallic box covered with appropriate front plate modules erected on / in wall/ ceiling as per pipe erected with following type of (I) For 6A Plug with 2-1.5 Sq.mm Cu. wire (f) With medium class rigid PVC Pipe and accessories - Cat_III	473.69	Rupees Four Hundred Seventy Three and Paise Sixty Nine only	One Point	947.38

52	1.000	No	Providing & erecting Switch board for Computer or electric apparatus consisting of following items in single board erected on PVC / Metal board with 3 mm thick PC (Polycarbonate) / Acrylic sheet erected as directed 1 no. 6A/16A universal plug-switch combined. 4 nos. 6A Switch 4 nos. 6A 5 pin Plug [B] For Modular Type Accessories Cat. III	1081.71	Rupees One Thousand Eighty One and Paise Seventy One only	One Number	1081.71
53	2.000	No	Decorative call bell Ting-tong box type 250 volts complete erected	68.68	Rupees Sixty Eight and Paise Sixty Eight only	One Number	137.36
54	7.000	No	Supplying and erecting led lamps with following wattage capacity of 220 to 240 voltage, minimum 15000 burning hours life, 500 V in built-surge protection, Polycarbonate diffuser, mounting suitable for E14 / E27 / B22 lamp holders, pf >= 0.5 (A) LED Lamps integral type, with PC diffuser suitable LAMP holder (iii) 10 to 15 watts	188.87	Rupees One Hundred Eighty Eight and Paise Eighty Seven only	One Number	1322.09
55	5.000	No	Miniature circuit breaker single pole 6A to 25A suitable to operate on 240 V A.C. system and having breaking capacity 10 KA to be erected in existing box. confirming to IS 8828/1996 with ISI Mark Cat-III	112.11	Rupees One Hundred Twelve and Paise Eleven only	One Number	560.55
56	1.000	No	Providing & erecting 240 V MCB double pole switch for lighting load (B Curve) having 10 KA breaking capacity & Confirming to IS :8828 in Existing box , having capacity (B) 40 Amp.- Cat-III	295.93	Rupees Two Hundred Ninety Five and Paise Ninety Three only	One Number	295.93
57	2.000	No	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, confirming to IS 13032 and BS 5486-1986 without MCB to house appropriate nos. of MCBs.(The DBs should be used of same company of MCB to be used) (A) Single phase 12 way SS double door	1492.78	Rupees One Thousand Four Hundred Ninety Two and Paise Seventy Eight only	One Number	2985.56
58	4.000	No	Providing & erecting Approved make Ceiling Fan with double ball bearing ISI mark with Condenser 230 volt A.C. 50 c/s, 1200 mm sweep complete having 3 blades with aluminium blades with , canopy & 30 cms. down rod erected on existing hook or Clamp with 24/ 0.2, 3 core flexible wire with earthing. (Make shall be approved by Engineer in charge)	1596.81	Rupees One Thousand Five Hundred Ninety Six and Paise Eighty One only	One Number	6387.24

59	1.000	No	Pipe type earthing having 150 cms.long and 2.5 cms. dia. Galvanised iron pipe with coupling and buch buried in specially prepared earth pit complete with necessary 8 SWG earth wire. For using salt and charcoal / coke as required for pipe type earthing.	540.35	Rupees Five Hundred Forty and Paise Thirty Five only	One Number	540.35
			<b>Dismntled Material Credit Rs. 0 will be deducted from 1 St R.A. Bill</b>				
Rupees Twenty Eight Lakh Seventy Two Thousand Seven Hundred Fourteen and Paise Seventy Seven only						Total Rs.	2872714.77

I \ We am \ are willing to carry out the work at ..... % above\ bellow percent ( Should be written in figures and words ) of the estimated rate mentioned above. Amount of My \ Our tender works put as under.

\* Estimated Amount

Put to tender Rs.....

Deduct.....%

Net Rs.....

In words.....

\* Estimated Amount

Put to tender Rs.....

Add.....%

Total Rs.....

In words.....

1.The Contractor shall exhibit a board with detailed specification and details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.

2.The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.

3.GST and Income tax TDS will be deducted at a source while making payments of bills

4.In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt.

G.R.: PRC-10/2017 Cement Consumption/16/C Date:11/05/2017 as stated in

S.O.R. therefore in R.C.C. items where there is a change as per actual mix design the cost

of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.

Signature of Contractor

Deputy Executive Engineer  
Panchayat R.& B. Sub Division  
Rajula

Executive Engineer  
Panchayat R.& B. Division  
Amreli