



Tender No. VED/Tech/JE-II/2142

DATE: 25.06.2026

Sub:- ARC for Erection and Maintenance of HT, LT & TC at Khodiyarnagar SDn and any other sub divisions under VISHWAMITRI EAST Division office.

SR. NO.	E urja Item Code	Description	Unit of Measurement	Estimated Rate (Rs)
1	9908000049	Augmentation / de augmentation of TC of any capacity including carting of TC from store to site, fixing of channels, supporting angles, bracing, cross arms clamps & cable wiring, Replacement of Distribution Box etc. The dismantled TC & Old Distribution Box should be credited to Lalbaug store.	No.	2855
2	9909000001	Carting of PSC pole at destination of site.	No.	378
3	9909000006	Carting of RSJ pole from West Division to site/ above 2kms	No.	536
4	9905010001	CONCRETING OF POLES, GUYS, ETC. INCLUDING COST OF CEMENT AND METAL AND WATER ETC. AS PER C.C.M-20 GRADE SPECIFICATION.	CMT	5995
5	9911000009	Cutting / Trimming of Tree Branch obstructing HT/LT line on one tree	Per Tree	60
6	9907000012	Dismantling of DP structure of PSC poles of 8Mtrs to 13Mtrs long	No.	1322
7	9907000013	Dismantling of DP structure of 8 to 13 MTR RSJ poles	No.	1910.5
8	9907000001	Dismantling of Guy set complete with crediting in store	No.	280.5
9	9907000009	Dismantling of ACSR/AAAC/Copper conductor & crediting dismantled material at Lalbaug store.	one cond per km	1055.5
10	9907000002	Dismantling of PSC pole including excavation & refilling of earth. Dismantled fabricated material should be credited separately at sub divisional store.	No.	581.5
11	9907000011	Dismantling of steel pole including excavation & refilling of earth. Dismantled fabricated material should be credited separately at Lalbaug store.	No.	974.5
12	9907000025	Dismantling of HT Aerial Bunch Cable 3-Wire (All Size) and crediting of materials to Lalbaug store.	Km.	22553.5
13	9907000025	Dismantling of Aerial Bunch Cable 1 P 2-Wire (All Size) and crediting of materials to Lalbaug store.	Km.	4812.5
14	9907000025	Dismantling of Aerial Bunch Cable 3 P 4-Wire (All Size) and crediting of materials to Lalbaug store.	Km.	12028.5
15	9902030019	Dismantling of double pole Structure Completely Excluding Guy and Earthing for any capacity X'mer on RSJ Poles and crediting of materials to the Lalbaug Store	No	5304.5
16	9902030020	Dismantling of double pole Structure Completely Excluding Guy and Earthing for any capacity X'mer on 200KG PSC Poles and crediting of materials to the Lalbaug Store	No.	4537
17	9902020012	Erection of double pole structure with mounting of AB switch, HG fuse, <b>8-11 mtrs steel pole</b> including excavation of pits, refilling of earth, fixing of channel, supporting angles, clamps, anti climbing devices, danger boards, insulators etc complete, painting of poles & fabricated material used in the poles and numbering with cost of paints as per standard specification but excluding erection of guy set and earthing.	No.	4171
18	9902020010	Erection of double pole structure with mounting of AB switch, HG fuse, <b>9-11 mtrs steel pole</b> including excavation of pits, refilling of earth, fixing of channel, supporting angles, clamps, anti climbing devices, danger boards, insulators etc complete, painting of poles & fabricated material used in the poles and numbering with cost of paints as per standard specification but excluding erection of guy set and earthing. ( <b>with one pole existing</b> )[4171-1949]	No.	2222
19	9902020013	Erection of double pole structure <b>8-9mtrs steel pole</b> including excavation of pits, refilling of earth, fixing of channel, supporting angles, clamps, anti climbing devices, danger boards, insulators etc complete, painting of poles & fabricated material used in the poles and numbering with cost of paints as per standard specification but excluding erection of guy set and earthing( W/O AB Switch)	No.	3821
20	9902020004	Erection of double pole structure with <b>mounting of AB switch, HG fuse, 8 mtrs 200kg PSC pole</b> including excavation of pits, refilling of earth, fixing of channel, supporting angles, clamps, anti climbing devices, danger boards, insulators etc complete, painting of poles & fabricated material used in the poles and numbering with cost of paints as per standard specification but excluding erection of guy set and earthing	No.	3179
21	9902020001	Erection of double pole structure 8mtrs 200kg PSC pole including excavation of pits, refilling of earth, fixing of channel, supporting angles, clamps, anti climbing devices, danger boards, insulators etc complete, painting of fabricated material used on poles and numbering with cost of paint as per standard specification but excluding erection of guy set and earthing ( <b>W/O A B Switch</b> )	No.	2644

22	9902040002	Erection of coil type earthing including cost of coal, salt etc but without cost of GI wire as per standard specification. 10kg salt+10kg coal	No.	605
23	9902030016	ERECTION OF DISTRIBUTION TRANSFORMER STRUCTURE ON 8-11 METRE SINGLE STEEL POLE	No	5305
24	9902040003	Erection of <b>GI pipe/GI plate</b> type earthing including cost of coal, salt etc but without cost of Gipline/Cipline/GI wire as per standard specification. 20kg salt+20kg coal	No.	781
25	9902040001	Erection of guy set including excavation of pit & refilling of earth as per standard specification with stay clamps, stay wire, anchor rod, turn buckle, eye bolt, guy insulator, cement concrete block etc.	No.	561
26	9902010001	Erection of PSC pole of 8m*200kg including excavation of pit & refilling of earth, fixing of cross arms, top fitting clamps, anti climbing devices, insulators etc complete & painting of fabricated material used on poles & numbering with cost of paint as per	No.	1163
27	9902010004	Erection of steel pole of 8, 9 & 11mtrs including excavation of pit & refilling of earth, fixing of cross arms, top fitting clamps, anti climbing devices, danger board, insulators etc complete & painting of steel pole & fabricated material used on poles &	No.	1949
28	9902010006	Erection of support pole PSC where erection of guy set is not feasible as per instruction of EIC including painting of poles.	No.	735
29	9902010007	Erection of support pole RSJ where erection of guy set is not feasible as per instruction of EIC including painting of poles.	No.	735
30	9902030003	Erection of double pole structure with mounting of AB switch, HG fuse, <b>Transformer</b> , LA, Dist box, <b>8mtrs 200kg PSC</b> pole including excavation of pit & refilling of earth, carting of transformer from store to site, fixing of channels, supporting angles, bracings	No.	9074
31	9902030007	Erection of double pole structure with mounting of AB switch, HG fuse, <b>Transformer</b> , LA, Dist box, <b>8,9 &amp; 11 mtrs steel</b> pole including excavation of pit & refilling of earth, carting of transformer from store to site, fixing of channels, supporting angles. <b>(With AB Switch)</b>	No.	10609
32	9902030009	Erection of double pole structure with mounting of AB switch, HG fuse, <b>Transformer</b> , LA, Dist box, <b>8,9 &amp; 11 mtrs steel</b> pole including excavation of pit & refilling of earth, carting of transformer from store to site, fixing of channels, supporting angles, [9855-1811]with one pole existing	No.	8660
33	9902030007	Erection of double pole structure without mounting of AB switch, HG fuse, <b>Transformer</b> , LA, Dist box, <b>8,9 &amp; 11 mtrs steel</b> pole including excavation of pit & refilling of earth, carting of transformer from store to site, fixing of channels, supporting angles. <b>(Without AB Switch) (9855-795)</b>	No.	9753
34	9911000222	FIXING OF SMC (1-Ph) AT CONSUMER INSTALLATION ( including cost of Fasteners etc.) FASTNERS)	No.	98
35	9911000223	FIXING OF SMC (3-Ph) AT CONSUMER INSTALLATION ( including cost of Fasteners etc.) FASTNERS)	No.	148
36	9911000019	INSTALLATION OF ENERGY METER & MM/SMC BOX WITH ELECTRICAL WIRING ON TRANSFORMER	No,	727
37	9911000026	Laying of Overhead LT Cable for Road Crossing, HT Line and Telephone Line (Per Span)	No.	263
38	9913000013	Laying/ Relaying of XLPE/PILC Cable per Meter (From Ground to Pole)	Mtr	60
39	9911000001	NUMBERING OF POLE WITH MATERIAL	No.	60
40	9911000071	PATROLLING OF HT/LT LINE - PER POLE	No	4
41	9911000228	PROVIDING (PAINTING/MARKAR ) CONSUMER No ON SMC/MMB IN URBAN AREA	No.	11.842
42	9906000003	Providing guarding to HT/LT line on Road/ Rail crossing	Mtr	70
43	9904010003	Replacement of pole mounted 1-ph/3-ph service connection box including reconnecting all connections	No.	244
44	9904010002	PROVIDING SINGLE PHASE SERVICE CONNECTION WITH PVC CABLE FROM TERMINAL POLE TO METERING POINT COMPLETELY	No.	397
45	9904010001	PROVIDING THREE PHASE SERVICE CONNECTION WITH PVC CABLE FROM TERMINAL POLE TO METERING POINT COMPLETELY	No.	546
46	9911000004	REBINDING & CLEANING OF 11 KV PIN/DISC INSULATOR	Per Pole	47
47	9908000050	REFITTING/REPLACEMENT OF LIGHTENING ARRESTORS	No.	37
48	9911000010	REFIXING AND CHANGING HEIGHT OF TOP FITTING X ARM IN PROPER POSITION WITH SHORT FALL BOLTS AND NUTS TO BE PROVIDING BYCONTRACTOR AND DRILLING OF ADDI. HOLES.	No.	73
49	9911000059	REJUMPERING WORK OF HT/LT LINE FOR SHACKLE POLE	Per Pole	98
50	9911000007	REPAIRING/ADJUSTING TENSION OF EXISTING GUY/STAY SET INCLUDING PROVIDING/REPLACEMENT OF STAY INSULATOR	No.	183
51	9908000168	REPLACEMENT OF 1-Ph METER WITH WIRING IN URBAN AREA	No.	58.13
52	9908000011	REPLACEMENT OF 100 KVA (OR LESS THAN 100 KVA)) DIST. BOX COMP. INCL. TRANSPORTATION AS PER SPECIFICATION.	No.	1224

53	9908000010	REPLACEMENT OF OLD DIST. BOX 200 KVA & ABOVE WITH MAKING ALL CONNECTIONS CRIMPING OF LUGS, NEUTRAL, ETC	No.	2203
54	9908000009	PROVIDING DO FUSE OR AB SWITCH ON DP (FOR ONE SET) WITH FABRICATION & COLOUR CODE JUMPER, INCLUDING PROPER ALIGNMENT OF AB SWITCH CONTACTS	Set	856
55	9908000007	REPLACEMENT OF LT X ARM INC. TRANSPORTATION.	No.	79
56	9911000221	REFIXING OF TOP FITTING IN PROPER POSITION	No.	49
57	9908000016	REPLACEMENT OF SINGLE PHASE OLD SERVICE BY NEW SERVICE INCL. SHORTFALL REEL INSULATORS, EGGINSULATORS, NAILS, FIXING FASTNERS ETC.	No.	98
58	9908000051	REPLACEMENT OF TOP FITTING	No.	60
59	9908000001	REPLACEMENT OF V X ARM PAINTING & TRANSPORTATION	No.	244
60	9903000004	RESTRINGING OF ACSR/AAC (PER SPAN)	Span	111
61	9907000025	Restringing of 11Kv Aerial Bunch Cable (All size) (PER SPAN) with accessory fittings	Span	330
62	9903000001	Stringing of 30mm <sup>2</sup> ACSR/34mm <sup>2</sup> , 55mm <sup>2</sup> AAAC for 11/22kV & LT lines including fixing of insulators, binding, jumpering etc.	one cond per km	2111
63	9903000007	Stringing of HT Aerial Bunched Cable ( All Size) including binding and Jumpering 3 Wire ( All Size)	Km.	45107
64	9903000005	Stringing of LT Aerial Bunched Cable 1 P 2 W ( All Size) including binding and Jumpering.	Km.	9625
65	9903000006	Stringing of LT Aerial Bunched Cable 3 P 4W ( All Size) including binding and Jumpering.	Km.	24057
66	9902050003	Providing & Fixing Heat Shrinkable Indoor/Outdoor 11 KV ABC Cable Joint Boxes for 70mm <sup>2</sup> & 95 mm <sup>2</sup> (Rate is for 1 Core)	No.	2300
67	9901000001	HT tapping from existing pole including fixing of cross arms, clamps, anti climbing devices, danger board, insulators etc complete & painting of fabricated material & numbering complete with cost of paint as per standard specification but excluding erection of Pole	No.	481
68	9901000002	LT line tapping-single phase	No.	51
69	9901000003	LT line tapping-three phase	No.	93
70	9907000014	DISMANTALLING OF HT/LT GUARDING WIRE	Meter	35
71	9909000002	CARTING OF LINE MATERIALS TO SITE (PER TRIP)	No.	953
72	9908000166	REPLACEMENT OF LT PIN/SHACKLE INSULATORS AT CUT POINT	No.	37
73	9908000452	Straightening of tilted PSC/RSJ Pole at pin point	No.	284
74	9908000453	Straightening of tilted PSC/RSJ Pole at tension point	No.	329
75	9908000454	Straightening of tilted D.P. Set (PSC / Girder pole) etc with refilling of stones, morum etc.	No.	810
76	9911000275	Painting of steel / RSJ pole-100X116 of 9 to 13 mtr (Excluding fabricated materials)	No.	1132
77	9911000276	Painting of steel / RSJ pole - 150X150 of 11 to 13 mtr (Excluding fabricated materials)	No.	1456
78	9911000274	Painting of all steel/MS fabricated materials on DP structure with transformer of PSC / RSJ pole (Excluding RSJ pole)	No.	776
79	9911000273	Painting of all steel/MS fabricated materials on DP structure (without transformer) of PSC/RSJ pole (Excluding RSJ pole)	No.	380
80	9911000271	Painting of steel / MS fabricated materials of PSC/RSJ Pole (HT Line)	No.	123
81	9911000272	Painting of steel/MS fabricated materials of PSC/RSJ Pole HT pole extension (HT Line)	No.	179
82	9911000231	Replacement of old jumper/binding/lugs etc from LA to DO fuse to transformer	Per jumper	60
83	9908000451	Replacement of 11 KV pin insulator by new pin insulator/composite pin insulator	No.	56
<b>TOTAL (AMOUNT) excluding GST</b>				<b>2499316.2</b>
<b>18 % GST</b>				<b>449877</b>
<b>TOTAL (AMOUNT) including GST</b>				<b>2949193.5</b>

Sign of Contractor  
With Rubber Stamp

Executive Engineer  
VED