

SCHEDULE-B

Sub: Supply of HT Booting, Sleeves (conductor cover), Bird Guard & HT EPR Tape in any scheme for transformers (including installation) of Rander Town -1 & 2 Sub Division under Rander Division and if required work to be carried out other sub division under Rander Division.

Sr. No.	Item Description	Item Code	Unit	Rate in Rs.	Amt in Rs.
1	Supply & fixing of up to 33 kV Conductor sleeve for Busbar to Drop out Fuse and Drop out fuse to Transformer H.T. including Busbar (12 mm sleeve) as per technical specification. (All Materials will be supplied by Agency)	9926000093	Per T/C	5600	
2	Supply & fixing of up to 33 kV Conductor sleeve for Busbar to Drop out Fuse and Drop out fuse to Transformer H.T. including Busbar (15 mm sleeve) as per technical specification. (All Materials will be supplied by Agency)	9926000094	Per T/C	6050	
3	Supply & fixing of Disc type Red Color FRP(Non-flammable) material with Weather resistant, Non-conductive bird guard OD=300 MM, ID=33 MM, Width =1.25 MM, one side cut from ID to OD. (All Materials will be supplied by Agency)	9926000095	No.	80	
4	Supply and Installation of 11/22 kV Distribution Transformers HT Terminal protector (UV Resistance) with using 95/120/150 sq.mm long barrel aluminum lug. (1Set = 3 No's i.e. on R, Y, B)	9926000086	Per set	1700	
5	Supply & Installation of HT EPR Tap on 11/22 kV Distribution Transformer with replacement of bare conductor by HT ABC conductor (DO bottom side to transformer) after removal of semiconductor by HT ABC (6 inch both side). HT ABC to be supplied by DGVCL. (1Set = 3 No's i.e. on R, Y, B)	9926000087	Per set	1800	
	TOTAL			10,00,000.00	
	% Above/Below of estimate amount.				
	Grand Total				
	In Words :				

Note: - All Rates Excluding of GST.

Executive Engineer (O&M)

DGVCL, Rander Division.